

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No. 13** on the **Ship "Durham"** Survey held at **London** Date **Aug to Oct 7** 18 **64**
 Master **J. C. Kerr**
 Tonnage **1286** Built at **Sunderland** When built **1844-8 Nov**
 By whom built _____ Owners **G. Marshall**
 Port belonging to **London** Destined Voyage **Calcutta**
 If Surveyed Afloat or in Dry Dock **Ship's Youngs' Dry Dock & London Dock**

Last Survey, No. **8211** Port **Sunderland**. Classed **13A** 8.6.4

REPAIRS *Now done, six upper seams of her bottom on each side Caulked, the whole of the seams of the bottom filled out with spun yarn - and the bottom sheathed with yellow metal on felt -*
Her Anchors and Chains have now been proved at the Society's Proving House -

Anchors	Weight	Chain
1 - 34" 2" 12 ea stock	32.2	300 fath of 1 7/8 tested to 63 1/2 tons
1 - 31" 3" 0 "	29.10	
1 - 34" 3" 19 "	32.6	
1 - 33" 1" 16 "	31.3	
Stream 10" 0" 23 "	12.4	

She has 90 fathoms of 1 1/8" Stream Chain - 90 fathoms of 11 inch Hawser - 90 fath of 7 and 90 fath of 6 inch Warps - Six Boats - Two suits of sails - Two S Pumps - a Steam Winch - and her Rigging of wire and Hemp -

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <i>good</i>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. } <i>Good and</i>
Lower Deck Beams & Fastenings } <i>good</i>	Ditto Ditto at other places	Sails } <i>buff</i>
Planksheers	Keelsons	Anchors No. of } <i>4 B. 10. 2 K</i>
Sheerstrakes	Clamps and Shelves	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter } <i>not caulked now</i>	Yellow metal	
	Copper on felt	

General Observations and Opinion,

She is in good and efficient condition, fit in my opinion to be classed 13A.1.

B. W. Wymouth

The Amount of Fee.....£..... is received by me,

Special.....

Certificate (if required) :

Committee's Minute *11th October* 18 *64*

Character assigned *13A.1*

(L & C. P.) Records
MT



© 2019

Lloyd's Register
 Fd 001649-0004