

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 370 Survey held at London Date 18 Feb 1864
 on the "Highflyer" (ship) Master P. S. G. Benest
 Tonnage 1012 Built at London When built 1861
 By whom built Greens Owners Greens &
 Port belonging to London Destined Voyage Sydney
 If Surveyed Afloat or in Dry Dock Greens Cover Dry Dock and Afloat.

Last Survey, No. 25900 Port London. Classed 13. A. 1.
 63

REPAIRS

Now done -

The ship stripped - chafed garboard and bilge strakes dubbed fair - New false keel 5 ins deep. 65 feet long of English Elm. fitted and fastened to main keel - ship hung in shores and caulked from keel to second beam on deck. inside of waterways. five new copper shut Bolts in Rides at Turn of Bilges. renewed - new head rails and truck boards. and Boat davit - her bottom re-sheathed with yellow metal on paper.

Present Condition of the

Decks <u>good when seen</u>	Treenails <u>good when seen</u>	Windlass and Capstan <u>good and</u>
Waterways <u>"</u>	Breasthooks and Stems <u>"</u>	Pumps <u>sufficient.</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame at the openings <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>"</u>	Ditto Ditto at other places <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Keelsons <u>"</u>	Anchors No. of <u>"</u>
Sheerstrakes <u>"</u>	Clamps and Shelves <u>"</u>	Cables <u>"</u>
Topsides <u>caulked</u>	Ceiling <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Rudder <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>	Yellow metal Copper <u>When put on Now done</u>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>good when tested -</u>	

In my opinion she is not eligible to remain as classed

The Amount of Fee.....£ : : is received by me,

Special..... 1 : 1 : -

Certificate (if required) : 5 : -

Committee's Minute 10th January 1865

Character assigned 13 A 1

Damage Fee £ 5.5.0



© 2019

Lloyd's Register Foundation

LON649-0174