

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 549 Survey held at London Date Jan<sup>y</sup> 24<sup>th</sup> 18 65  
 on the S. "Solent" Master Paige  
 Tonnage 732 Built at Cowes When built 1857  
 By whom built White Owners J. Shepherd  
 Port belonging to London Destined Voyage China  
 If Surveyed Afloat or in Dry Dock Limelight dock

Last Survey, No. 25290 Port London Classed 13 A 1  
 REPAIRS Diagonal Bents (P. 5.) 63

In consequence of Damage see Report  
 The yellow metal sheathing stripped off and the ship  
 hung in shores, the keel and butts of outside planking  
 on bilges and buttocks additionally bolted, dovetail  
 plates refastened and mainpiece of Rudder renewed  
 with English Oak. The strake of deck next the main  
 deck waterways (Leak) taken up and rabbeted to the  
 same and a new strake of pine worked inside it.  
 upper deck additionally fastened, False keel fore and  
 aft renewed. Two deck beams renewed with Eng. Oak.  
 Recaulked throughout and resheathed with yellow  
 metal over felt. Added

Six pairs of Hanging knees to Hold Beams P.S.O.  
 and one breast Hook in tween decks.

## Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	"
Planksheers	"	Keelsons	"	Anchor No. of	"
Sheerstrakes	"	Clamps and Shelves	"	Cables	"
Topsides	"	Ceiling	"	Hawsers and Warps	"
Wales	"	Rudder	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper <u>F &amp; Y M</u> When put on <u>now</u>			

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Where tested good

This vessel is now in good condition and  
 is eligible in our opinion to remain as  
 classed 13 A 1

The Amount of Fee.....£ 2 : - : is received by me,

Special damage 6 : 6 : -

Certificate (if required)

Committee's Minute 3<sup>rd</sup> March 18 65

Character assigned 13 A 1

second repair

MT

Thos. W. Brown

John Maxwell

R. J. Reed



© 2019

Lloyd's Register  
 Foundation  
 LON 649-0240



26670202

Decay

on Starboard bow; one length of Waterway,  
one of Shelf, two lengths of Clamps and two  
half beams renewed with English Oak;  
three beam arms new of the same -

Thos. W. Wain

John Maxwell



© 2019

Lloyd's Register  
Foundation