

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 620 on the *37 Spheroide* Survey held at *London* Date *Jan<sup>y</sup> 7<sup>th</sup> 1865*  
 Tonnage *254* Built at *Bermuda* Master *Wellard* When built *1826*  
 By whom built \_\_\_\_\_ Owners *Scrutton &*  
 Port belonging to *London* Destined Voyage *West Indies*  
 If Surveyed Afloat or in Dry Dock *Limehouse dry dock*

Last Survey, No. *26139* Port *London* Classed *A 1* in *Red*  
*S.S.B. 6 yrs 64*

## REPAIRS

Part of the counter planks renewed with Dantzic Fir, upper piece of stem with English Oak, one piece of waterway on port bow of the same also new windlass and comings, upper and lower deck shelves bolted with galvanized iron. Resaulted from metal up.

Added, two pairs of diagonal knee and one pair of strap riders extending from upper deck clamps to floors.

## Present Condition of the

| Decks                         | <i>Good</i> | Treenails   | <i>Good</i> | Windlass and Capstan       |
|-------------------------------|-------------|---|-------------|----------------------------|
| Waterways                     | "           | Breasthooks and Stemson                           | "           | Pumps                      |
| Comings                       | <i>new</i>  | Transoms, Pointers, and Crutches                  | "           | Boats                      |
| Upper Deck Beams & Fastenings | "           | Timbers of the Frame at the openings              | "           | Masts, Yards, &c.          |
| Lower Deck Beams & Fastenings | "           | Ditto Ditto at other places                       | "           | Sails                      |
| Planksheers                   | "           | Keelsons  | "           | Anchors No. of             |
| Sheerstrakes                  | "           | Clamps and Shelves                                | "           | Cables                     |
| Topsides                      | "           | Ceiling   | "           | Hawsers and Warps          |
| Wales                         | "           | Rudder  | "           | Standing & Running Rigging |
| Plank (Bottom) and Counter    | "           | Copper <i>1 1/2 x 1/2</i> When put on <i>1863</i> |             |                            |

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *where tested good*

This vessel is now in good condition fit for the conveyance of dry and perishable cargoes to and from all parts of the world and is eligible in our opinion to remain as classed *A 1 in Red*

The Amount of Fee.....£ *10* : is received by me.

Special..... *1* : *1* : *1*

Certificate (if required) \_\_\_\_\_

Committee's Minute *4<sup>th</sup> April* 18 *65*

Character assigned *A 1 in Red*

*record repair*



© 2019

Lloyd's Register Foundation  
 LON649-0285