

REPORT of SURVEY for REPAIRS.

2nd Continuation.

26806

No. in Reg. Book. **No.** 169 Survey held at London Date March 16th to 18 65 April 4th
on the S. "Orient" Master J. Harris
Tonnage 1032 Built at London When built 1853
By whom built Bilbe & Co Owners Thompson &
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock Nelson dry dock

Last Survey, No. 26077 Port London Classed 8 A 1
Cont 61 — 3 64 expired

REPAIRS

In consequence of damage see Special Report; the yellow sheathing stripped off, the trenails in way of fore rigging to midships on each side renewed, the ship recaulked throughout and diagonally sheathed with 1 1/4 inch American Elm (in lieu of Reders) over Felt and the yellow metal sheathing renewed —

Continuation, to complete No 2. survey

Scraped and dubbed bright from metal line to waterway seam air courses and limbers cleared, trenails and bolts driven out. The beam ends bored and windlass examined — The opening being dispensed with see letter from the Secretary dated March 2nd 1865

Two lengths of lower deck waterway on port side and one plank of ceiling above the same renewed with Oregon Pine, six knees in way of same refitted & bolted —

Present Condition of the

Decks	<u>Good</u>	Trenails	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	"
Planksheers	"	Keelsons	"	Anchors No. of	<u>3 x 1 x 2</u>
Sheerstrakes	"	Clamps and Shelves	"	Cables	<u>300 fms 1 1/8</u>
Topsides	"	Ceiling	"	Hawsers and Warps	<u>Sufficient</u>
Wales	"	Rudder	"	Standing & Running Rigging	<u>do</u>
Plank (Bottom) and Counter	"	Copper <u>Y.M.</u> When put on <u>now</u>			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

This vessel is now in good condition and is eligible in our opinion to be continued 5 A 1 from 1861

The Amount of Fee.....£ 5: — — is received by me,

Special damage 5: 5: —

Certificate (if required) : 5: —

Committee's Minute 23rd May 18 65

Character assigned Cont 1 for 5 years from 1861

Thos. W. Mawson
John Maxwell



© 2019

Lloyd's Register

LDN649-0363