

REPORT of SURVEY for REPAIRS.

1st Continuation

No. in Reg. Book. **No.** 148 Survey held at **London** Date **August 16th 1864**
 on the **S. "Maori"** Master **Roberts**
 Tonnage **489** Built at **Sunderland** When built **1851**
 By whom built _____ Owners **Stuart & Co**
 Port belonging to **London** Destined Voyage **Australia Dock**
 If Surveyed Afloat or in Dry Dock **Lincolns dry dock & St Katharines,**

Last Survey, No. **26385** Port **London** Classed **13th 1** expired **5.64**

REPAIRS

Now done; the yellow metal sheathing stripped off, the outside planking from the light water mark to the waterway seam scraped or dubbed bright; proper listings left out in the hold (the timbers all found sound) and treenails and bolts driven out as per Rule section 54 —

One plank of wales and one on buttock new of Teak & Eng. Oak, ten Deckbeams and one half beam of Teak, an inner waterway (6 inches) worked of Dantzic Fir, the upper deck from the mainmast forward renewed with yellow pine.

Present Condition of the

Decks weather new	Treenails pt new good	Windlass and Capstan good
Waterways good	Breasthooks and Stemson "	Pumps "
Comings pt new	Transoms, Pointers, and Crutches "	Boats "
Upper Deck Beams & Fastenings "	Timbers of the Frame at the openings "	Masts, Yards, &c. from mast maker
Lower Deck Beams & Fastenings "	Ditto Ditto at other places "	Sails sufficient
Planksheers "	Keelsons "	Anchors No. of 3 x 1 x 2
Sheerstrakes "	Clamps and Shelves "	Cables 300 fms good
Topsides "	Ceiling "	Hawsers and Warps sufficient
Wales "	Rudder "	Standing & Running Rigging dw
Plank (Bottom) and Counter "	Copper It & JMC When put on now	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. **good where tested**

This vessel having now complied with the whole of the requirements of the Rules sect 54 1st survey and being in a good and efficient state of repair is eligible in our opinion to be continued **4th 1** from 1864

The Amount of Fee.....£ 3 :- is received by me,

Special..... 5: 5: -

Certificate (if required) : 5: -

22/8/64

Thos. W. Wain

Committee's Minute **18th August** 18 **64**

Character assigned

Cont'd 1 for 4 years from 1864
second repair
WMA

Thos. Wain

Lloyd's Register Foundation

26938 Son

Retreenailed twenty one strakes from the
gunwale down all fore and aft; the
ship hung in stores, recaulked through-
out and resheathed with yellow metal
on Felt -

Thos. M. Wauw

Windlass stripped and found good

SWR
P. M.

R. J. B.



© 2021

Lloyd's Register
Foundation