

27062

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 260 Survey held at London Date Oct 5<sup>th</sup> 20<sup>th</sup> 1865.  
on the Barque Tigris Master Thos<sup>d</sup> Wheelan.  
Tonnage 393 Built at Sunderland When built 1851.  
By whom built 429 Owners Smith & Co.  
Port belonging to Scarbro Destined Voyage West Indies  
If Surveyed Afloat or in Dry Dock "New Crane"

Last Survey, No. 26254 Port London. Classified A. 1.  
64

## REPAIRS

chiefly from damage. (See Report) Stripped off the whole of the Yellow Metal Sheathing, hung her in shores unbolted the foremast length of Keel, two lengths of Garb<sup>d</sup> Strake on the Port side, lengthened the Scarph in the adjoining length of Keel. Cut out all defects found in the planks outside, and some from the inside. Introduced a new fore Keel piece of English Elm. (Caulked from the Keel to the Wales.) and two lengths of Garb<sup>d</sup> Port side fore<sup>d</sup> refitted the stanchions to the deck and Hold beams. Resheathed with Yellow Metal on felt up to 15ft 6 —

### Present Condition of the

	<i>in good order</i>	<i>where seen good</i>	<i>in good order</i>
Decks	"	Treenails	Windlass and Capstan
Waterways	"	Breasthooks and Stemson	Pumps
Comings	"	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	Masts, Yards, &c. Condition, how ascertained, <i>from the deck</i>
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	Sails
Planksheers	"	Keelsons	Anchors No. of 3
Sheerstrakes	"	Clamps and Shelves	Cables
Upsides	"	Ceiling	Hawsers and Warps
Wales	"	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	"	Copper <i>Yellow Metal</i> on felt <i>now</i>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <i>good where tested.</i>		

I am of opinion She is entitled to remain as Classd A. 1.  
Samuel Presing.

The Amount of Fee.....£ 1 : — : — is received by me,

Special..... 2 : 2 : —  
Certificate (if required) : 5 : —

Committee's Minute 27<sup>th</sup> October 18 65

Character assigned A. 1  
second repair



*Tigres*



© 2021

Lloyd's Register  
Foundation