

27238

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 287 Survey held at London Date Jan'y 5th 26 1866
on the Ship Alchymist Master S. Thier
Tonnage 539 Built at Sunderland When built 1859.
By whom built Thomson Owners Jolly & Co.
Port belonging to London Destined Voyage Australia.
If Surveyed Afloat or in Dry Dock Lower Globe & London docks afloat

Last Survey, No. 26324 Port London. Classed 10. A. 1.
64

REPAIRS

Sighted the Yellow metal, patched and repaired it. took off the hawse boxes both sides with the hawse pipes. overhauled the caulking behind, leaded the joints. fitted a new hawse pipe on the port side. Caulked the topsides, introduced a New Mizzen mast, and refitted the rigging. Caulked busses and seams of waterway both sides.

Present Condition of the

| | | |
|---|---|---|
| Decks <u>in good order</u> | Treenails <u>where seen good</u> | Windlass and Capstan <u>in good order</u> |
| Waterways <u>"</u> | Breasthooks and Stenson <u>"</u> | Pumps <u>"</u> |
| Comings <u>"</u> | Transoms, Pointers, and Crutches <u>"</u> | Boats <u>"</u> |
| Upper Deck Beams & Fastenings <u>firm</u> | Timbers of the Frame at the openings <u>"</u> | Masts, Yards, &c. <u>New mizen mast</u> |
| Lower Deck Beams & Fastenings <u>"</u> | Ditto Ditto at other places <u>"</u> | Condition, how ascertained <u>from the Deck</u> |
| Planksheers <u>"</u> | Keelsons <u>"</u> | Sails <u>"</u> |
| Sheerstrakes <u>"</u> | Clamps and Shelves <u>"</u> | Anchors No. of <u>3</u> |
| Topsides <u>"</u> | Ceiling <u>"</u> | Cables <u>"</u> |
| Wales <u>"</u> | Rudder <u>efficient</u> | Hawsers and Warps <u>"</u> |
| Plank (Bottom) and Counter <u>"</u> | Copper <u>Fir & y. M^{ts}</u> When put on <u>1864</u> | Standing & Running Rigging <u>"</u> |
| General Observations and Opinion, | Caulking of Bottom, Deck, & Waterways. <u>good</u> | |

I am of opinion this Vessel is eligible to remain as
Class'd 10. A. 1.
Samuel Presons

The Amount of Fee.....£..... is received by me.

Special..... / : / : -

Certificate (if required) : 5 : -

Committee's Minute 9th February 1866

Character assigned 10 A 1



© 2021

Lloyd's Register
Foundation

LONG 650-0291

Alchymist



© 2021

Lloyd's Register
Foundation