

27245

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 70 Survey held at London Date Jan'y 18th Feb'y 2^d 1866.
on the Ship Saladin Master J. Rankin.
Tonnage 782 Built at Sunderland When built 1851.
By whom built _____ Owners Henderson.
Port belonging to London Destined Voyage Calcutta.
If Surveyed Afloat or in Dry Dock "King & Queen" and East India docks (afloat.)

Last Survey, No. 26532 Port London. Classed 13. A. 1.
Cont 64 - 64

REPAIRS

Sighted the yellow metal sheathing and found it in good condition. Caulked from the metal line to the deck, the buttocks, and waterway seams. - fitted two new Catheads, new cheeks to the Mizzen Mast, lifted the Rudder, fitted a new upper brace to it of iron. altered the main Hatchway to Hold Beams. for taking in Boilers &c. i.e. made the Beam on the aft side of it, in three lengths, (instead of one as before.) secured it and put all in order. -

Present Condition of the

Decks <u>in good order</u>	Treenails <u>good where seen</u>	Windlass and Capstan <u>in good order</u>
Waterways "	Breasthooks and Stemson "	Pumps "
Comings "	Transoms, Pointers, and Crutches "	Boats "
Upper Deck Beams & Fastenings <u>firm</u>	Timbers of the Frame at the openings "	Masts, Yards, &c. "
Lower Deck Beams & Fastenings "	Ditto Ditto at other places "	Condition, how ascertained <u>from the deck</u> "
Planksheers "	Keelsons "	Sails "
Sheerstrakes "	Clamps and Shelves "	Anchors No. of <u>3</u> "
Topsides "	Ceiling "	Cables "
Wales "	Rudder <u>efficient</u> "	Hawsers and Warps "
Plank (Bottom) and Counter "	<u>Copper</u> <u>plated</u> <u>in felt</u> <u>When put on 1864</u>	Standing & Running Rigging "
General Observations and Opinion, <u>Caulking of Bottom, Deck, & Waterways. good.</u>		

I am of opinion this Vessel is entitled to remain as class'd

13. A. 1.

Samuel Persons.

The Amount of Fee.....£..... is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 9th February 18 66

Character assigned Cont 9 A 1



© 2021

Lloyd's Register Foundation