

27247

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 48 Survey held at London Date 19th to 26th January 18 66.
on the Ship "Lealandia" Master John Foster.
Tonnage 1032 Built at New Brunswick When built 1837.
By whom built _____ Owners Fletcher.
Port belonging to London Destined Voyage Bombay.
If Surveyed Afloat or in Dry Dock Union Dry Dock and East India Dock.

Last Survey, No. 26365 Port London Classed 7. A. 1.
SS 64 - 585 Cont. 64 for 2488.64

REPAIRS

Now done:-
Bottom sighted and the Yellow metal patched.
Caulked the Waterway seams, and two next seams of Deck, on both sides, also the whole of the Butts of the Main Deck.

Renewed the Strake of deck next the Waterway, on both sides, - from 13 feet the fore-side of the Break of Stoop to the after end of the Forecastle - with Yellow Pine. - The Beams, Inner Thine Waterway, and Deck, thus exposed, were found to be in very good condition.

Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways	Good	Breasthooks and Stemson	Good	Pumps	Good where seen.
Comings		Transoms, Pointers, and Crutches	Good	Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Ditto Ditto at other places	where	Condition, how ascertained	By Enquiry & observation.
Planksheers	where	Keelsons		Sails	Good and
Sheerstrakes		Clamps and Shelves		Anchors No. of	sufficient
Topsides		Ceiling	seen.	Cables	
Wales	seen.	Rudder		Hawsers and Warps	where seen.
Plank (Bottom) and Counter		Copper <u>F.Y.M.</u> When put on <u>1864</u>		Standing & Running Rigging	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where seen.

She is now in good and efficient condition, and fit, in my opinion, to remain as classed.

The Amount of Fee.....£ : : is received by me,

Special..... 1 : 1 : 2

Certificate (if required) : 5 : 2

Committee's Minute 9th February 18 66

Character assigned

Cont 2 A 1 M.D.

© 2021

Lloyd's Register
Foundation

LNH56-0298