

27314

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 944 Survey held at London Date 5th March 18 66
on the Ship "Art Union" Master J. A. Polson.
Tonnage 748 Built at Sunderland When built 1857
By whom built _____ Owners Lidgett & Sons.
Port belonging to London Destined Voyage China
If Surveyed Afloat or in Dry Dock Young's Dry Dock and East India Dock

Last Survey, No. 26480 Port London Classed 13. A. 1.
4. 64

REPAIRS

Now done:- Cleared the Keelson fore and aft, and examined it. Dubbed the Keelson down under the foremast, cut off and re-clenched the keel-bolts, and worked and fastened a Hog-piece 12" x 14" over that part of the Keelson which had been reduced, for a length of 40 feet, of Greenheart.

The following have been renewed:-

Forward on the Starboard side:- Seven first futtocks, two second futtocks, four filling Timbers and eight Cross and Keel Chocks with English Oak; and thirteen fore-hoods of filling with Greenheart.

Forward on the Port side:- Three first futtocks, seven second futtocks, four filling Timbers, and twelve Cross and Keel Chocks with English Oak; and fourteen fore hood-ends of filling with Greenheart.

Introduced one pair of diagonal Riders forward, P.S.O.

Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good where seen.
Waterways		Breasthooks and Stemson		Pumps	
Comings	where	Transoms, Pointers, and Crutches	where	Boats <u>4H?</u>	Good and sufficient
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings	seen	Ditto Ditto at other places	seen	Condition, how ascertained <u>By inquiry & observation</u>	where seen.
Planksheers		Keelsons		Sails	
Sheerstrakes	partly caulked	Clamps and Shelves	1854 some renewed none	Anchors No. of _____	
Topsides		Ceiling <u>Some new.</u>		Cables	
Wales	Copper Yellow metal When put on a pair felt	Rudder	Good where tested.	Hawsers and Warps	
Plank (Bottom) and Counter		Caulking of Bottom, Deck, & Waterways		Standing & Running Rigging	

She is now in good and efficient condition, and fit, in our opinion, to remain as classed.

The Amount of Fee.....£ 2 : - : - is received by me,
Special..... 3 : 3 : -
Certificate (if required) : : -

Committee's Minute 13th March 18 66

Character assigned 13 A 1
renewed 4th
W.H.

27314. Jan.

forward, and through bolted them, together with all the Iron Breasthooks forward with Yellow metal.-

Bottom sighted and the Yellow metal sheathing patched.- 125 Sheets of Yellow metal sheathing on felt, renewed, on each Box, in wake of the foregoing repairs, and the Bottom caulked and tested under it.-

Williamson.
Stornish



© 2021

Lloyd's Register
Foundation