

27325

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 887 Survey held at London Date Feb'y 17<sup>th</sup> March 1<sup>st</sup> 1866.  
on the Barge Minnie Master David Blacke  
Tonnage 408 Built at Newcastle When built 1864.  
By whom built — Owners Adamson &  
Port belonging to London Destined Voyage Japan  
If Surveyed Afloat or in Dry Dock "Bull head" & West-India Docks.

Last Survey, No. 7427 Port Newcastle Classed Ex. B.S. 12. A. 1.  
Iron frame planked 64

## REPAIRS

Stripped off the whole of the Yellow Metal sheathing drifted out a galvaniz'd bolt from each side at the upper part of bilge (in midps) found both of them good, at present, two others galvaniz'd have been put in, and plugg'd over as before. — Caulked from Keel to Copper line, and resheathed with Yellow Metal on felt. — It appears that she damaged her Cargo coming home, in consequence of the Cement giving way, and the bilge water getting mix'd with it, choking the pumps &c, it found its way through the joints of the Ceiling.

Nearly the whole of the Ceiling has been lifted, and the planks, frames, bolts &c clean'd or clear'd of the Old Cement, and fir wash boards 2 ins thick, have been now fitted in the openings, between the floors, or frames, and below the iron stinger, at the turn of the bilge; and the planks &c, &c, inside, have been again plaster'd over with fresh Cement, the Ceiling all refitted, secured, and Caulked, or chinz'd as a preventive

Present Condition of the	Cement,	the Ceiling all refitted, secured, and <u>Caulked</u> .	or chinz'd as a <u>preventive</u>		
Decks	in good order	Treenails	Galv'd Bolts where seen good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	Pumps	tanks fitted below
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from the deck
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 3
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder	efficient	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	Yel <sup>d</sup> Met <sup>l</sup> on felt When put on	Standing & Running Rigging	"
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.			good	

I am of opinion she is entitled to remain as Class'd  
Ex. B.S. — 12. A. 1.  
Samuel Piesons.

The Amount of Fee.....£ : : is received by me,  
Special..... 2 : 2 : —  
Certificate (if required) : 5 : —

Committee's Minute 13<sup>th</sup> March 1866  
Character assigned 12 A 1



Name date

1811 9th 10 1878 10 1810 11



© 2021

Lloyd's Register  
Foundation