

REPORT of SURVEY for REPAIRS.

2nd Continuation

No. 25492 Survey held at Garmouth Date Sep 23rd 18 65
on the S^a "Isis" Master J. Smith
Tonnage 175 Built at Garmouth When built 1836
By, whom built J. Scott & Co Owners J. Scott & Co
Port belonging to Garmouth Destined Voyage Mediterranean
If Surveyed Afloat or in Dry Dock Fellows dry dock & afloat

Survey, No. 25492 Port London Classed 12 A 1 expire
Rest 53 - 8 63

IRS

Scraped bright from light water mark to waterway beam, a strake of topsides taken out all fore and aft on each side, a short plank on each buttock, a listing cut out all fore and aft on each side in the ceiling at the turn of the bilge, the caulking tested under the metal and treenails and bolts driven out to complete the Rule Sec 54. 2nd Survey.

The strake of topsides on each side renewed with English Oak and Red Pine, also two topside planks on starboard, two lengths of sheerstrake and one of plank sheer, nine toptimbers and four roughtruss of English Oak. Two buttock planks of English Oak - On port side, fourteen toptimbers and two roughtruss of English Oak also two lengths of sheerstrake, one of plank sheer and one fore hood of blackstrake, one topside plank of Red Pine and eight planks of deck renewed - Recaulked from the metal line up.

Present Condition of the

Decks	Good	Treenails	Good	Windlass and Capstan	Good
Waterways	Good	Breasthooks and Stemson	Good	Pumps	2 of Iron
Comings	Good	Transoms, Pointers, and Crutches	Good	Boats	Good
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	when seen Good	Masts, Yards, &c.	} sufficient
Lower Deck Beams & Fastenings	Good	Keelsons	Do	Sails	} sufficient
Planksheers	at new	Clamps and Shelves	Do	Anchors No. of	3 x 1 x 2
Sheerstrakes	"	Ceiling	Do	Cables	180 fms
Topsides	"	Rudder	Do	Hawsers and Warps	} sufficient
Wales	Good	Copper	TM	Standing & Running Rigging	} sufficient
Wink (Bottom) and Counter	Good	When put on	1864		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested

This vessel is now in a good and efficient state of repair and having fulfilled the whole of the requirements of the Rules Section 54. 2nd Survey is eligible in my opinion to be continued 5 A 1 from 1861

Amount of Fee.....£ 2 : - : - is received by me,

£5.10.6 Special..... 3 : 3 : -

Certificate (if required) : 2 : 6

Committee's Minute 20th March 18 66

Character assigned

Cont A 1 for 5 years from 1861
renewed repair

Detained until the owner decided whether he would go for the A 1 or A 1 in Red character

© 2021

Lloyd's Register Foundation