

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 368 Survey held at London Date March 29th 18 66
 on the S "Marshal Peltisier" Master Pearne
 Tonnage 612 Built at Sunderland When built 1855
 By whom built Owners Blyths & Co
 Port belonging to London Destined Voyage Mauritius
 If Surveyed Afloat or in Dry Dock in Larter's dry and West India Dock

Last Survey, No. 25720 Port London - Classed 10 A1 expired 68

REPAIRS

Stripped Yellow metal sheathing; hung in shores; scraped and dubbed bright from light mark to waterways inclusive; drove out trenails as per rule; opened at each end by the removal of a listing equal to one fifth the length of the ship; windlass unhung, stripped, examined, and found good; chains ranged, examined and found good.

Renewed several broken Yellow metal bolts in Riders and Knees; re-trenailed from Bilges to Planksheers (26 strokes on each side); caulked from Keel to Planksheer and re-sheathed with Yellow metal over felt.

The timbers of the frame where exposed were in a satisfactory condition

Present Condition of the

Decks	<u>Good</u>	Treenails <u>pt new</u>	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	Condition, how ascertained, from enquiry & as seen from deck
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Sails	"
Planksheers	"	Keelsons	"	Anchors	No. of <u>3 B, 1 S, 2 K</u>
Sheerstrakes	"	Clamps and Shelves	"	Cables	"
Topsides	"	Ceiling	"	Hawsers and Warps	"
Wales	"	Rudder	"	Standing & Running Rigging	"
Plank (Bottom) and Counter	"	Copper <u>F & Y M</u> When put on <u>1866</u>			
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways. <u>when tested Good</u>			

Is now in good and efficient condition and having fully complied with the Rules Sec 54 1st survey is in our opinion eligible to be continued A1 for 3 years from 1865.

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 4 : 4 : 0

Certificate (if required) : 5 : -

Committee's Minute 10th April 18 66

Character assigned

Cont A 1 for 3 years
from 1865
record repair

John Maxwell
R. J. Reed.



© 2021

Lloyd's Register
 Foundation

Lon680-0407