

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 138 Survey held at London Date Sept^r 23rd 18 65
 on the B^M "Caroline" Master R. Turner
 Tonnage 341 Built at London When built 1841
 By whom built ✓ Owners Tottam & Co
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock In West India & Nelson dry dock

Last Survey, No. 26556 Port London Classed 12 A1 expired
 F.Y.M. & pt S. 64 Rest 57. & 11.64

REPAIRS

Scraped bright and drove out bolts and treenails from metal line upwards, took out a listing in after hold one fifth the length of the vessel; the timbers exposed forward by the removal of ceiling and the upper course of bottom surveyed in accordance with the Rules in anticipation of continuation in November 1864, (see report of that date) windlass partly stripped being new at that date; chains ranged, examined and found good and efficient.

Renewed the whole of the Iron hanging knee throat bolts to upper deck from break of Quarter deck forward; took out a lodging knee of wood & substituted it with an iron one; lifted Bowsprit, re-leaded stem head and renewed standards to windlass bits

Present Condition of the

Decks <u>Good</u>	Treenails <u>pt new</u> <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stenson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame at the openings <u>"</u>	Masts, Yards, &c. <u>Condition, how ascertained, from inquiry & as seen from deck</u>
Lower Deck Beams & Fastenings <u>not seen</u>	Ditto Ditto at other places <u>"</u>	Sails <u>"</u>
Planksheers <u>"</u>	Keelsons <u>"</u>	Anchor's No. of <u>3 B, 1 S, 1 K</u>
Sheerstrakes <u>"</u>	Clamps and Shelves <u>"</u>	Cables <u>examined</u> <u>"</u>
Topsides <u>"</u>	Ceiling <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Rudder <u>"</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>not seen</u>	Copper <u>F.Y.M.</u> When put on <u>1864</u>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>Good where tested</u>	

Is now in good and efficient condition and having fully complied with the Rules Sec. 54 upon this and with former survey is in our opinion eligible to be continued A1 for 3 years from the end of 1865

The Amount of Fee.....£ 4 : — : — is received by me,

Special..... 3 : 3 : 0

Certificate (if required) : 5 : —

Committee's Minute 8th May 18 66

Character assigned Cont'd for 3 years from 1865

John Maxwell
R. J. Reed



© 2021

Lloyd's Register Foundation

Long 650-0455