

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 352 Survey held at London Date Oct<sup>r</sup> 26<sup>th</sup> Dec<sup>r</sup> 4<sup>th</sup> 1865  
 on the Barge Alexandrina Master Thos Bradford  
 Tonnage 294 Built at Aberdeen When built 1848  
 By whom built 251 Owners Falconer  
 Port belonging to London Destined Voyage Lagos  
 If Surveyed Afloat or in Dry Dock "Gun Dock" & Hermitage Basin

Last Survey, No. 26102 Port London in red. Classed S.S. C. R. I. 1864  
 64

## REPAIRS

New Rough tree rails, new bulwark berthing, thirteen rough tree and the whole of the poop stanchions, with rails fore and aft all renewed, chiefly from damage. — On the Starboard side from defects, three lengths of plank sheer, and the whole of the covering board to poops (East India Sea) and seven lengths of deck planks (Yellow pine) renewed. —

Port side the after length of covering board and one of plank sheer (forward Sea), four lengths of deck planks. — and the whole of the middle line deck planks, from the main mast and Comings to main hatchway, with some short lengths in other places. — Gave her a New Rudder, main piece English Oak, new bolsters or channels to rigging, New landing blocks, Hawsepipe Port side refitted and bolted. — Caulked the Topsides and deck, and put all in order. — sighted the yellow metal sheathing, patched and repaired it. in dry dock

### Present Condition of the

Decks	in good order	Treenails	where seen good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	from the deck
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained,	"
Plank sheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of 3	"
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder New	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper, 4 Mel on felt When put on 1864	"	Standing & Running Rigging	"
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. good.				

I am of opinion this vessel is entitled to remain as  
 class'd in red S.S. C. R. I. from  
 1864.

Samuel Presnall.

The Amount of Fee.....£ : 10 : — is received by me,  
 Special..... / : / : —  
 Certificate (if required) : 5 : —

Committee's Minute 15<sup>th</sup> May 18 66

Character assigned in red  
record repair



© 2021

Lloyd's Register  
 Foundation

LON650-0467



Alexandrina



© 2021

Lloyd's Register  
Foundation