

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. *65* No. *25864* Survey held at *London* Date *19th Feb^r Oct^r 17th 1865*
on the *Barque East Lothian* Master *John Drysdale*
Tonnage *388 3/4* Built at *Kincardine* When built *1853*
By whom built *—* Owners *Alexander & Co.*
Port belonging to *Leith* Destined Voyage *Colombo*
If Surveyed Afloat or in Dry Dock *"Bull head."*

Last Survey, No. *25864* Port *London* Classed *Rest^d 62. 5. A. 1.*
63

REPAIRS

Stripped off the whole of the yellow metal sheathing.
lifted the main mast which proved defective, also (33 ft - (in length))
of main keelson, found bad or decay'd, between the main
and Foremast, opened the air courses, lifted the limbers.
scraped the inside planking bright; introduced a new length
of keelson (Amⁿ white Oak 13 3/4 x 18). a new main mast of
yellow pine. refitted the rigging. Resheathed with yellow metal
on felt up to 16 ft.

Supplied her with the following new chain cables and
two anchors of *one of 14. 2. 18 = 16 tons one of 9. 2. 4 = 11. 6 - Proof -*

*Tested at our Own Establish^y 120 fms of 1 7/16 Chain
= to 37 2/10 tons.*

Present Condition of the

| | | | | | |
|-------------------------------|----------------------|--|------------------------|-----------------------------|----------------------|
| Decks | <i>in good order</i> | Treenails | <i>where seen good</i> | Windlass and Capstan | <i>in good order</i> |
| Waterways | " | Breasthooks and Stemson | " | Pumps | " |
| Comings | " | Transoms, Pointers, and Crutches | " | Boats | " |
| Upper Deck Beams & Fastenings | <i>firm</i> | Timbers of the Frame at the openings | " | Masts, Yards, &c. | <i>New main</i> |
| Lower Deck Beams & Fastenings | " | Ditto Ditto at other places | " | Condition, how ascertained. | <i>firm the deck</i> |
| Planksheers | " | Keelsons <i>Bolts all renewed (throughout) found bad. - 1 1/4 iron</i> | " | Sails | <i>two new</i> |
| Sheerstrakes | " | Clamps and Shelves | " | Anchors No. of <i>3</i> | " |
| Topsides | " | Ceiling | " | Cables | <i>part new</i> |
| Wales | " | Rudder <i>efficient</i> | " | Hawsers and Warps | " |
| Plank (Bottom) and Counter | " | Copper <i>Yel^m with on felt When put on Now</i> | " | Standing & Running Rigging | " |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. *good where tested.*

*I am of opinion she is entitled to remain
as class'd *Rest^d 5. A. 1.*
*Samuel Persons.**

The Amount of Fee.....£ *1* : : is received by me,

Special..... *2* : *2* :

Certificate (if required) : *5* :

Committee's Minute *Sept 7th* 18 *66*

Character assigned *Rest^d 5 A 1*

record repair

mt



© 2019

Lloyd's Register
Foundation

LN 651-0134

East Lothian



© 2019

Lloyd's Register
Foundation