

27885

# REPORT of SURVEY for REPAIRS.

and Continuation 1st survey

No. in Reg. Book. **No.** 915 Survey held at **London** Date **18 66**  
on the **B8 "Susan Bayley"** Master **Frankland**  
Tonnage **158** Built at **Ipswich** When built **1853**  
By whom built **Bayley** Owners **Banner Bros**  
Port belonging to **London** Destined Voyage **East of Africa**  
If Surveyed Afloat or in Dry Dock **in Bridge & West India Docks**

Last Survey, No. **18703** Port **London** Classed **13 A1**  
REPAIRS **c.f** **4.64**

Stripped Yellow metal sheathing; scraped bright from light mark to waterways inclusive; drove out trenails as per Rule; opened at ends by the removal of a listing equal to one fifth the length of the vessel, windlass, unhooking, stripped examined and found good; chains ranged on deck & examined and 90 fathoms added; see other side.

Renewed one length of main keelson of Teak fastened with yellow metal bolts, and two lengths of ciling of English Oak; caulked from keel to Topsides inclusive and re-sheathed with copper over felt.

Present Condition of the						
Decks	Good	Treenails	pt new	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from enquiry & as seen from deck
Planksheers	"	Keelsons	pt new	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of	2 B 1 S 1 R
Topsides	"	Ceiling	pt new	"	Cables	"
Wales	"	Rudder	"	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper over felt	When put on	1866	Standing & Running Rigging	"
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways. where tested				Good

Is now in good and efficient condition and having complied with the Rules Sec. 54 1st Survey is in our opinion eligible to be continued A1 for 4 years

The Amount of Fee.....£ 2 : - : } is received by me. **John Maxwell**  
Special..... 3 : 3 : } **R. J. Reed.**  
Certificate (if required) : : }

Committee's Minute **16th November 1866**

Character assigned **Cont A1 for 4 years**  
**WMA**



Luscar Bay

Chains now supplied

	in	tested to	Tons	date					
15 fathoms	1 1/6	to	20 3/10	30th Oct <sup>r</sup> 1866	at	Lloyd's	London,	signed	L.P.
30 "	1 1/6	"	20 3/10	30th Oct <sup>r</sup> 1866	"	"	"	"	L
45 "	1 1/6	"	20 3/10	30th Oct <sup>r</sup> 1866	"	"	"	"	L

John Maxwell  
R. F. Reed,



© 2019

Lloyd's Register  
Foundation