

Half-time Survey.

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 57 Survey held at London. Date 24th Jan^y to 11th Feb^y 1864.
 on the Ship "Dartmouth" Master T. A. Elsdon.
 Tonnage 933 Built at Dundee. When built 1859 (7. Mo.)
 By whom built _____ Owners Somes. Bros.:-
 Port belonging to London. Destined Voyage Sydney.
 If Surveyed Afloat or in Dry Dock Equal Dry Dock and London Dock.

Last Survey, No. 27289 Port London. Classed 14 A 1.
 2.66.

REPAIRS Now done:- The Yellow Metal sheathing stripped off the Bottom, and the Vessel caulked from the keel to the fourth seam of deck. Resheathed the Bottom with Yellow Metal over felt. Middle line cleared and the Limbers lifted on each side, fore and aft, the Keelsons, Floors, Stemson and Sternson, examined and found good. The Windlass, a patent Iron one, appeared to be in good working condition. Removed the side-cants to the front of the Poop, and caulked the deck under them. Bushed the upper Pintle of the Rudder, and refastened the Poop-drafts with galvanized Iron dunnage.

Present Condition of the

Decks <u>part caulked</u>	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps <u>2 K^o</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>5--</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>By Enquiry and Observation.</u>
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 B. 15. 2 K.</u>
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>Gal. a felt</u> When put on <u>now.</u>	Standing & Running Rigging

General Observations and Opinion, _____ Caulking of Bottom, Deck, & Waterways, good where tested.

She is now in good and efficient condition, and fit, in our opinion, to remain as classed.

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : W. H. W.

Certificate (if required) _____

Committee's Minute 19th February 18 64

Character assigned 14 B. W. H. W.

record Y. M.



© 2019

Lloyd's Register Foundation

LOU 651-0 439