

28099

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 217 Survey held at London Date 6th Feby & 22^d 1867.
 on the Ship Northfleet Master W^m Symington
 Tonnage 895 951 Built at Northfleet When built 1853.
 By whom built — Owners Freeman &
 Port belonging to London Destined Voyage China
 If Surveyed Afloat or in Dry Dock "Carters" & East India Docks

Last Survey, No. 27217 Port London Classed 14.A.1.
65-

REPAIRS

Stripped off the whole of the yellow metal sheathing. Caused up to Copper line. (The Topsides are reported to have been caulked last June) and at the same time on the Portside a new Knightshead was introduced of hard wood. also twelve new bulwark Stanchions, new berthing a new Cathead, on the Starb^d side. New taffrail. Chain plate bolts were all renewed at the same time, with a size larger. — New main mast of Teak now fitted. the rigging all made good. Resheathed with Yellow metal on felt of a lighter sort, in anticipation of its having to be renewed, on the expiration of her clasp, or on her return. about three fourths of a strake of the upper deck on the Starb^d side renewed, on account of the seam being wide and open below. —

Present Condition of the

| | | |
|---|---|---|
| Decks <u>in good order</u> | Treenails <u>where seen good</u> | Windlass and Capstan <u>in good order</u> |
| Waterways <u>"</u> | Breasthooks and Stemson <u>"</u> | Pumps <u>"</u> |
| Comings <u>"</u> | Transoms, Pointers, and Crutches <u>"</u> | Boats <u>"</u> |
| Upper Deck Beams & Fastenings <u>firm</u> | Timbers of the Frame at the openings <u>"</u> | Masts, Yards, &c. <u>"</u> |
| Lower Deck Beams & Fastenings <u>"</u> | Ditto Ditto at other places <u>"</u> | Condition, how ascertained <u>"</u> |
| Planksheers <u>"</u> | Keelsons <u>"</u> | Sails <u>"</u> |
| Sheerstrakes <u>"</u> | Clamps and Shelves <u>"</u> | Anchor No. of <u>3</u> <u>"</u> |
| Topsides <u>"</u> | Ceiling <u>"</u> | Cables <u>"</u> |
| Wales <u>"</u> | Rudder <u>efficient</u> <u>"</u> | Hawsers and Warps <u>"</u> |
| Plank (Bottom) and Counter <u>"</u> | Copper <u>Fell & Y. Mth</u> When put on <u>now</u> | Standing & Running Rigging <u>"</u> |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

I am of opinion she is entitled to remain as Clasp'd 14.A.1.
 Samuel Pessons

The Amount of Fee.....£ 2 : - } is received by me.

Special..... 2 : 2 }

Certificate (if required) : :

Committee's Minute 1st March 1867

Character assigned 14.A.1

record WMS.



© 2019

Lloyd's Register Foundation

LON 651-0461