

REPORT of SURVEY for REPAIRS.

Composite

No. in Reg. Book. **No.** 268 Survey held at London Date April 11th 1867
on the Ship "Douglas Castle" Master M^r Ritchie
Tonnage 678 Built at Glasgow When built 1864
By whom built _____ Owners Jas^r Skinner & Co
Port belonging to Glasgow Destined Voyage China
If Surveyed Afloat or in Dry Dock Canal Drydock

Last Survey, No. 2264 Port Glasgow Classed 14 D. 1.
REPAIRS Now done, the yellow metal sheathing stripped off the bottom, the bottom Caulked and resheathed with Yellow metal.

Two planks of Ceiling at the upper turn of bilge on the Starboard side, one on the Port side, and one each side in the flat in the after Hold, taken up and the timber boards lifted in midships. Four Yellow Metal Nut and Screw bolts, which fastened the the bottom planks, on each side, driven out. Found the holes through which the bolts passed in good condition, no perceptible difference had, apparently taken place in either the bolts or the holes. The is Cemented to the upper turn of bilge, caused some of the Cement to be cut out from various places, found it adhering well to the frames and planking, and both in good condition where exposed. The bolts have been replaced, the Cement made good and the Ceiling refitted where it had been lifted.

Present Condition of the		Treenails <u>None</u>		Windlass and Capstan	
Decks		Breasthooks and Stemson		Pumps	} <u>Good</u>
Waterways	} <u>Good</u>	Transoms, Pointers, and Crutches		Boats	
Comings		Timbers of the Frame at the openings		Masts, Yards, &c.	<u>Good</u>
Upper Deck Beams & Fastenings	} <u>Good</u>	Ditto Ditto at other places		Condition, how ascertained	<u>by enquiry</u>
Lower Deck Beams & Fastenings		Keelsons	} <u>Good</u>	Sails	
Planksheers	} <u>Good where seen</u>	Clamps and Shelves		Anchors No. of	} <u>Good and</u>
Sheerstrakes		Ceiling		Cables	
Topsides		Rudder		Hawsers and Warps	<u>Sufficient</u>
Wales		<u>Yellow metal</u>		Standing & Running Rigging	
Plank (Bottom) and Counter	<u>Caulked</u>	Copper	When put on <u>now</u>		
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.		<u>Good</u>	

She is now in good and efficient condition, fit in my opinion to remain classed 14 D. 1. and to be marked B.S. 1867 in the Registry Book.

B. W. Wainwright

The Amount of Fee.....£ - : - : is received by me,
Special..... / : / :
Certificate (if required) : : :

Committee's Minute 30th April 18 67
Character assigned 14 D. 1.

record G.M. M.S.

