

28256

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 16 Survey held at London Date April 6th to 30th 1867.
on the Bth "Ballarat" Master R Craighead
Tonnage 685 Built at Aberdeen When built 1852.
By whom built _____ Owners Tanner and Co
Port belonging to London Destined Voyage Auckland
If Surveyed Afloat or in Dry Dock Bull-head dry Dock, and East India St^{rs}

Last Survey, No. 26985 Port London. Classed 12.A.1 (Cont 64.0)
REPAIRS Now done on account of Damage. P. 65.

Sighted bottom the Yellow metal stripped.
Renewed on the Port side, 14 Rough-tree Stanchions with Iron-bark, the Rail to ditto with American-elm; also topgallant berthing and Rail &c; on the Forecastle a shake of deck each side next covering board with yellow pine, and a transporting chock on each horn with Dautrie-oak;
Renewed the Steering Wheel, and added a new patent steering apparatus.
Caulked from keel to plank-sheers, also round the Stanchions &c, and resheathed the Bottom with Yellow metal on Felt.
Renewed one Stream Anchor 9" 2" 2. cut 22 lbs

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps <u>Two</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>Three</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>inspⁿ</u>
Plank-sheers <u>Caulked</u>	Keelsons <u>Not seen</u>	Sails <u>part new</u>
Sheerstrakes <u>D^o</u>	Clamps and Shelves	Anchors No. of <u>3 B.P. 11</u>
Upsides <u>D^o</u>	Ceiling <u>part seen</u>	Cables
Sides <u>D^o</u>	Rudder <u>Had good</u>	Hawsers and Warps
Plank (Bottom) and Counter <u>D^o</u>	Copper <u>Y.M. on F</u> When put on <u>new</u>	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>Good where tested</u>	

She is now in good and efficient condition and fit in my opinion to remain as Classed. Viz. A. 1.
Joseph Keen.

The Amount of Fee.....£ 2 : - : 7 is received by me,
Special...../ - / - 0
Certificate (if required) : :

Committee's Minute 10th May 1867
Character assigned Cont^d 8th 1

record damage repair