

28292

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 154 on the Ship Hastings. Survey held at London Date Feb'y 27 April 6<sup>th</sup> 1866.  
Master Mc Queen.  
Tonnage 541 Built at Sunderland When built 1855.  
By whom built — Owners Oliver &  
Port belonging to London Destined Voyage Bushire  
If Surveyed Afloat or in Dry Dock "Princes" & the London Clocks.

Last Survey, No. 26357 Port London. Classed Cont<sup>d</sup> / 64. 3. A. 1.  
64

## REPAIRS

Stripped off the whole of the Yellow metal Sheathing. -  
condemned the Stem, upperpart of Apron, fillings &c in connection  
the whole being badly decay'd, likewise the main piece of Rudder.  
and two of the upper deck beams near to fore hatchway. - three  
planks Starb<sup>d</sup> side aft (found wormed), cut out some defects from  
the timbers where exposed on the Starb<sup>d</sup> Quarter, a new length fitted  
of false Keelson. New Stem, part Apron. New main piece to  
Rudder. (Iron Bark) Stem of English Oak. three new planks of Dan'gk  
Oak (one of them forming a butt-plk) Hung her in Shores. Caulked from  
Keel to Gunwale. took off the Knee of the head, and all in  
connection. Naval hoods also with the hause pipes. Head Tails, &c  
refitted, repaired, and secured the whole. Gunmoning to Bowsprit,  
made good & the ends of deck under the forecastle. -  
Resheathed with Yellow metal on felt.

## Present Condition of the

Decks	in good order	Treenails	where seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	See other side
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from the DH
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of	3
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	new 14 7/8 by 13 5/8	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	4 1/2 Mells When put on	now	Standing & Running Rigging	"

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

I am of opinion She is entitled to remain as class'd  
Cont<sup>d</sup> 3. A. 1 in / 64  
Samuel Davies.

The Amount of Fee.....£ 2 : — : } is received by me.

Special..... 3 : 3 : }

Certificate (if required) : : }

Committee's Minute 24<sup>th</sup> May 18 66

Character assigned Cont<sup>d</sup> 3 A 1

second repair



© 2021

Lloyd's Register Foundation

LN652-0052



28292 Len

New mizen topmast, New main Yard, topsail and  
topgall Yard. Mizzen topsail Yard. Crotch Yard and  
New mizen rigging.

Samuel Parsons.



© 2021

Lloyd's Register  
Foundation