

REPORT of SURVEY for REPAIRS.

No. in 7. Book. No. C Survey held at London Date 20th May 25 1867
on the Ship Scotland Master W. H. Knight
Tonnage 1170 Built at Quebec When built 1861
By whom built — Owners Adamson &
Port belonging to Glasgow London Destined Voyage Bombay
If Surveyed Afloat or in Dry Dock Britannia dry dock, also afloat in the Victoria docks.

Survey, No. 27401 Port London Classed J. A. I.
PAIRS 66

Sighted the yellow metal, dress'd it up, and in places renailed it where necessary. - In the port bidge found some planks had got wormed, where the yellow metal sheathing had got rubb'd off. Split out a part of two planks towards the after end, and introduced a plank of Amⁿ Elm 5½ to 6 ins thick, and about 25 ft in length, and cut out some wormed places further forward, and let in pieces 1¼ thick. Caulk'd and made all good and efficient, and resheath'd with yellow metal on felt. - Recommended the Burns, to split out a length of deck next the waterway on each side the Ship, on account of the seam being open below, which they have engaged to do, and have put two new deck planks on board for that purpose of improving the caulking at those parts of the deck pointed out. Two lengths of the false hull renew'd.

sent Condition of the		in good order		where seen good		in good order	
ks				Treenails		Windlass and Capstan	
terways	"			Breasthooks and Stenson	"	Pumps	"
ings	"			Transoms, Pointers, and Crutches	"	Boats	"
er Deck Beams & Fastenings	firm	"		Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
er Deck Beams & Fastenings	"			Ditto Ditto at other places	"	Condition, how ascertained	from the deck "
ksheers	"			Keelsons	new last year	Sails	"
rstrakes	"			Clamps and Shelves	"	Anchors No. of	3 "
sides	"			Ceiling	"	Cables	"
es	"			Rudder	efficient	Hawsers and Warps	"
ak (Bottom) and Counter	"			Copper	Felt & 4M When put on 1866	Standing & Running Rigging	"

eral Observations and Opinion, Caulking of Bottom, Deck, & Waterways. good

This Ship being now (as far as seen) in good condition
I am of opinion she is entitled to remain
as Class'd J. A. I.
Samuel Persons

Amount of Fee.....£ 4 : - : is received by me
Special..... 1 : 1 :
Certificate (if required) : 5 :

Committee's Minute 31st May 1867
Character assigned J A I MAS.