

28333

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 973 Survey held at London Date 11th May June 1st 1867.
 on the Ship Art Union Master J. Madron.
 Tonnage 748 Built at Sunderland When built 1857.
 By whom built _____ Owners Lidgett &
 Port belonging to London Destined Voyage Hong Kong
 If Surveyed Afloat or in Dry Dock Britannia dry dock & in the East India docks.

Last Survey, No. 27314 Port London. Classed 13. A. 1.
 66

REPAIRS

Stripped off the whole of the Yellow Metal Sheathing. Caulked from Keel to Copper line, the butts of topsides, &c. the seams having been caulked in Calcutta about five months since. renewed three up and down bolts in one of the hold beams on the Port side, introduced a teak beam (extra) below the Cabin Cant to Post secured it at the sides with iron hanging knees. drove out two or three trenails for inspection from the bilges, they proved good. wedged up a good quantity inside at the points. six bolts put into bobstay knee. and cutwater better secured, with some extra bolts. three lengths of deck planks renewed (Starb^d side forew^d) butts of deck overhauled, overhauled the masts. new cross tree and trespel tree fitted to the main mast, two new cross trees to the Foremast, dumb cleat to the Rudder, and some Chain and preventer plate bolts renewed. Head rails all made good, likewise the bulwark berthing, and resheathed the bottom with Yellow metal on felt, as before.

Present Condition of the

| | | |
|---|---|---|
| Decks <u>in good order</u> | Trenails <u>where seen good</u> | Windlass and Capstan <u>in good order</u> |
| Waterways " | Breasthooks and Stemon " | Pumps " |
| Comings " | Transoms, Pointers, and Crutches " | Boats " |
| Upper Deck Beams & Fastenings <u>firm</u> | Timbers of the Frame at the openings " | Masts, Yards, &c. " |
| Lower Deck Beams & Fastenings " | Ditto Ditto at other places " | Condition, how ascertained " |
| Planksheers " | Keelsons " | Sails " |
| Sheerstrakes " | Clamps and Shelves " | Anchors No. of <u>3</u> " |
| Topsides " | Ceiling " | Cables " |
| Wales " | Rudder <u>efficient</u> | Hawsers and Warps " |
| Plank (Bottom) and Counter " | Copper <u>Yellow metal on felt</u> When put on <u>now</u> | Standing & Running Rigging " |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested.

This vessel being now in good condition. I am of opinion she is entitled to remain as Class'd viz 13. A. 1.

Samuel Presions

The Amount of Fee.....£ — : — : is received by me.

Special..... / : / : ASD

Certificate (if required) : :

Committee's Minute 7th June 18 67Character assigned 13 A 1record 4/11 M.S.

© 2021

Lloyd's Register
Foundation

LON652-0089