

# REPORT of SURVEY for REPAIRS.

28408

No. in Reg. Book. **No.** 167 Survey held at London Date 24<sup>th</sup> April to 1<sup>st</sup> June 1867.  
 on the Ship "Agamemnon" Master Mauder  
 Tonnage 1431 Built at London When built 1833  
 By whom built Green Owners R. & H. Green  
 Port belonging to London Destined Voyage Bombay  
 If Surveyed Afloat or in Dry Dock Green's Lower dock and East India dock

Last Survey, No. 27505 Port London Classed Rest. 63. for 7 yrs - 5.86.

## REPAIRS

Now done:- Bottom sighted the Yellow metal sheathing patched and painted with Peacock's patent Paint. Overhauled the faulking of the Butts of Topsides in places.

Doubled the Main-deck with two inch Dantzig-deals, upon the best hair-felt, and fastened it with 7/8 inch galvanized Iron dunnop-bolts, 9 ins long. Renewed five Beam-ends on the Portside of the Main-deck with Pitch-pine.

Thoroughly caulked the flat of Main deck before working the doubling, and the "Doubling" has also been well faulked.

## Present Condition of the

Decks <u>filled and doubled; now</u>	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps <u>2 H<sup>o</sup></u>
Comings	Transoms, Pointers, and Crutches	Boats <u>4 H<sup>o</sup></u> } <u>good where seen</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>By inquiry &amp; observation</u>
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 B. 15. 216</u> } <u>good and sufficient</u>
Topsides <u>faulked &amp; Butts overhauled</u>	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>7 1/2</u> in. When put on <u>1866</u>	Standing & Running Rigging } <u>where seen</u>
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	

She is now in good and efficient condition, and fit, in our opinion, to remain classed: A. 1.

The Amount of Fee.....£ 3 : 1 : 0 is received by me,  
 Special..... 2 : 2 : 0  
 Certificate (if required) : 5 :

Committee's Minute 5<sup>th</sup> July 18 67  
 Character assigned Rest 7 A 1



© 2021

Lloyd's Register Foundation

LON652-0145