

28503

REPORT of SURVEY for REPAIRS.

1st Continuation

No. in Reg. Book. **No.** 862 Survey held at Gf Garmouth Date August 3rd 1867
on the 4th "Arab" Master _____
Tonnage 189 Built at Garmouth When built 1841
By whom built _____ Owners Scott & Co
Port belonging to Garmouth Destined Voyage Mediterranean
If Surveyed Afloat or in Dry Dock Fellows dry dock

Last Survey, No. 25366

Port Lon

Classed 12 A 1

express

Rest 58 — 8

4.43.

REPAIRS

The yellow metal sheathing stripped to the light water mark and at various parts of the bottom to test the caulking which proved good, scraped bright from waterway stem to light water mark, trenails and bolts driven out as per Rule also listings cut out at both ends of the ship and the timbers proved all good, the Windlass stripped Chains ranged and all minor clauses of the Rule fully complied with —

The upper course of bottom recaulked and resheathed with yellow metal, ceiling repaired, windlass relined, main rigging renewed —

Present Condition of the

Decks	Good	Trenails	Good	Windlass and Capstan	Good
Waterways	do	Breasthooks and Stemson	do	Pumps	do
Comings	do	Transoms, Pointers, and Crutches	do	Boats	do
Upper Deck Beams & Fastenings	do	Timbers of the Frame at the openings	do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	do	Ditto Ditto at other places	do	Condition, how ascertained	by report
Planksheers	do	Keelsons	do	Sails	sufficient
Sheerstrakes	do	Clamps and Shelves	do	Anchors No. of	3 x 1 x 2
Topsides	do	Ceiling	do	Cables	sufficient
Wales	do	Rudder	do	Hawsers and Warps	do
Plank (Bottom) and Counter	do	Copper <u>FW</u> When put on <u>63 & 67</u>		Standing & Running Rigging	do

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

good where tested

This vessel is now in a good and efficient state of repair, and having fulfilled the whole of the requirements of the Rules see 54 Survey Not is eligible in our opinion to be continued 3 A 1

The Amount of Fee.....£ 2 : — : is received by me.

Special..... 3 : 3 : —

Certificate (if required) : 2 : 6

Committee's Minute 20th August 1867

Character assigned

Cont^d A 1 for 3 years
from 1867

Thos. W. Wain



© 2021

Lloyd's Register Foundation

LN652-0224

Exps 2-7

28503. Jan.

Custom House measurements

Length 94.1
Breadth 22.4
Depth 13.7 -

P. W. M.



© 2021

Lloyd's Register
Foundation