

REPORT of SURVEY for REPAIRS.

285-16

No. in Reg. Book. **No.** 387 Survey held at London Date 12th August 1867
 on the Ship "Hindson Castle" Master N. Price
 Tonnage 1074 Built at Sunderland When built 1857
 By whom built _____ Owners R. Green
 Port belonging to London Destined Voyage Falcutta
 If Surveyed Afloat or in Dry Dock Green's Upper dock and East India dock

Last Survey, No. 2756 Port London Classed 13 A 1 7/66

REPAIRS

Now done: On the starboard side, renewed five lower frame timbers and six cross-chocks, and parts of fourteen strakes of ceiling, ranging from the Sheelson upwards and from shifts abreast the Fore-hatch to the Skenson, with Teak and English Oak.

On the Port side, renewed four lower frame timbers six cross-chocks and one heavy filling timber with Teak and English Oak. About the same quantity of ceiling renewed as on the opposite side.

The Yellow metal sheathing renewed in way of the repairs, the bottom being first caulked. The Treemails in the new work new of English Oak and Locust. Repaired the Foremast.

Present Condition of the

Decks	Treenails <u>Some new</u>	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps <u>2</u> <u>new</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>4</u> <u>new</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>By inquiry and observation</u>
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>36</u> <u>15</u> <u>1</u> <u>K</u>
Topsides	Ceiling <u>Some new</u>	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter <u>Part pulked</u>	Copper <u>F & V. M.</u> When put on <u>1865</u>	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	

She is now in good and efficient condition, and fit, in my opinion, to remain classed: 13 A 1.

The Amount of Fee.....£ 3 : — : 7 is received by me,

Special..... 3 : 3 : 7

Certificate (if required) : 5 :

Committee's Minute 20th August 1867

Character assigned 13 A 1

W. Williams



© 2021

Lloyd's Register Foundation

LON652-0235