

28526

REPORT of SURVEY for REPAIRS.

Recd 6 May

No. in Reg. Book. **No.** 576 Survey held at London Date 23 July Augt 16th 1867
on the Barque Priscilla Master George Brown
Tonnage 253 Built at Wells When built 1858
By whom built _____ Owners Bullard &
Port belonging to London Destined Voyage Natal
If Surveyed Afloat or in Dry Dock "Up^r Globe" & London docks

Last Survey, No. 27713 Port London Classed 10. A. 1.
9.66

REPAIRS

Condemned the whole of the main Keelson found decayed except the after length, a short length of dead wood at the fore end a length of limber strake port side aft, and a short length of ceiling forward. — Gave her a new Keelson (now) of East India Teak a short length of deadwood, English Oak. the length of limber strake starboard. — Keelson sided 15 ins moulded 15 ins. Bolts 1 1/8 y, metal, — fitted a liner over the Keelson in wake of main hatchway, refitted the hold beam stations, resheathed keel & garb'd strakes, both sides, after caulking garb'd seams, hanging her &c. — remainder of metal sighted, and the vessel overhauled inside and outside. —

Present Condition of the

Decks <u>in good order</u>	Treenails <u>where seen good</u>	Windlass and Capstan <u>in good order</u>
Waterways "	Breasthooks and Stemson "	Pumps "
Comings "	Transoms, Pointers, and Crutches "	Boats "
Upper Deck Beams & Fastenings <u>firm</u>	Timbers of the Frame at the openings "	Masts, Yards, &c. "
Lower Deck Beams & Fastenings "	Ditto Ditto at other places "	Condition, how ascertained <u>from the Deck</u> "
Planksheers "	Keelsons "	Sails "
Sheerstrakes "	Clamps and Shelves "	Anchors No. of <u>3</u> "
Topsides "	Ceiling "	Cables "
Wales "	Rudder <u>efficient</u> "	Hawsers and Warps "
Plank (Bottom) and Counter "	Copper <u>2 1/4 lb</u> When put on <u>1865</u>	Standing & Running Rigging "

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

This Vessel being now in good condition, I am of opinion she is entitled to remain as class'd 10. A. 1.
Samuel Merwin,

The Amount of Fee.....£ : 10 : } is received by me,
Special..... 2 : 2 : }
Certificate (if required) : : }

Committee's Minute 23 August 1867

Character assigned 10 A
record repairs M.A.S.