

Half Time Survey

REPORT of SURVEY for REPAIRS.

28535

No. in Reg. Book. **No.** 33 Survey held at London Date July 25th 1867
 on the B^K "William & Jane" Master Copple
 Tonnage 406⁵⁹/₁₀₀ Built at Sunderland When built 1853
 By whom built W Pile Owners Smart &
 Port belonging to London Destined Voyage Demerara
 If Surveyed Afloat or in Dry Dock Lincolin (Dry Dock) London (Dock)

Last Survey, No. 28025 Port London Classed PA.1.
SS 64.5 Red A.1.

REPAIRS

now done, The Yellow Metal Stripped, two midship pieces of 14 $\frac{1}{2}$ x 15" Main Keelson of Teak and 9 in hog of American Oak, renewed: new steps to main and mizen masts; windlass stripped and unhung; the pintles of rudder off, and refitted; caulked from keel to upper edge of wales and resheathed with Yellow Metal on Felt.

The peaks cleared and examined, and the Main Mast renewed

Decks	Treenails	Windlass and Capstan	good
Waterways	Breasthooks and Stenson	Pumps	
Comings	Transoms, Pointers, and Crutches	Boats	good
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.	
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained	where
Planksheers	Keelsons	Sails	
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 D. 1 S 2 K</u>	seen
Topsides	Ceiling	Cables	
Wales	Rudder	Hawsers and Warps	
Plank (Bottom) and Counter	Copper <u>F&YM</u> When put on <u>now</u>	Standing & Running Rigging	

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. good where tested

She is now in good condition, fit in our opinion for the safe conveyance of dry cargoes to and from all parts of the world, and to remain as classed Red A.1.

The Amount of Fee.....£ 1 : - : is received by me.

Special..... 2 : 2 : 8

Certificate (if required) : 5 :

Committee's Minute 27th August 1867

Character assigned Red record G. M. M.P.S.

B. W. Wainwright



© 2021 Lloyd's Register Foundation