

Half Time Survey

REPORT of SURVEY for REPAIRS.

28599

No. in
Reg. Book.

No.

Survey held at

London

Date

Aug 7 to 26

18

67

on the

"Bk Rifleman"

Master

G Parson

Tonnage

346

Built at

Sunderland

When built

1860

By whom built

Briggs

Owners

Shepherd

Port belonging to

London

Destined Voyage

Japan

If Surveyed Afloat or in Dry Dock

Union Dry Dock & West India Dock

Last Survey, No.

26546

Port

Lon.

Classed

13 A. I.

REPAIRS

now done,

The yellow metal stripped, and in accordance with the new Rule for Half time Survey the hold has been cleared, stages made, air courses and limbers cleared, treenails driven out in various parts of the vessel and a portion of the topsides scraped bright; the windlass unhung and stripped, the chains ranged and examined, found good and sufficient, and other requirements attended to - The stemson knee renewed with Eng. Oak and the foremost piece of hog keelson with Teak - faulked from keel to plank sheer and the bottom resheathed with Yellow Metal on Felt

Present Condition of the

Decks

Waterways

Comings

Upper Deck Beams & Fastenings

Lower Deck Beams & Fastenings

Plank sheers

Sheerstrakes

Topsides

Wales

Plank (Bottom) and Counter

Treenails

Breasthooks and Stemson

Transoms, Pointers, and Crutches

Timbers of the Frame at the openings

Ditto Ditto at other places

Keelsons

Clamps and Shelves

Ceiling

Rudder

Copper T. & Y. M. When put on now

Windlass and Capstan

Pumps

Boats

Masts, Yards, &c.

Condition, how ascertained

Sails

Anchors No. of 3 B. S. 2 K

Cables

Hawsers and Warps

Standing & Running Rigging

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

She is now in good and efficient condition, fit in our opinion to remain as classed 13 A. I. and to be marked in the Register Book (HT 67).

The Amount of Fee.....£ - : - : is received by me,

Special..... 2 : 2 :

Certificate (if required) : :

Committee's Minute 13th September 18 67

Character assigned

13 A. I.

HT 67 M.S.

[Signature]
B. W. Wraymouth
Lloyd's Register
Foundation