

28643

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 56 Survey held at London Date Augt 29th Sep^r 16 1867
 on the Barque City of Carlisle Master Wm Hill
 Tonnage 815 Built at Sunderland When built 1853
 By whom built _____ Owners Crouch &
 Port belonging to Bristol Destined Voyage _____
 If Surveyed Afloat or in Dry Dock "King & Queen" dry dock and Shadwell Basin
 Last Survey, No. *1235 Port Milford Classified Cont^d 9. A. 1.

REPAIRS

Stripped off the whole of the yellow metal sheathing
 caulked from keel to gunwale, double holed up the butts
 and seams, plugged up four treenail holes and a bolt
 hole, found left open in the bottom on the starb^d side,
 improved or made good the stopwater to Post.
 Renewed a hold beam bolt, yellow metal, found broken.
 The Foremast proved rotten. lifted it and gave her one
 of yellow pine, and made good all in connection, trespel
 trees &c. - Rigging &c. -

Resheathed with yellow metal on felt. Cut out some
 defects found in the deck &c. and fitted graven pieces where
 necessary.

Present Condition of the

Decks	in good order	Treenails	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	Masts, Yards, &c.	New Fore Mast, main new last year
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from the Dic
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors	No. of 3 &c.
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder	efficient	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	Fer ^r & y ^l m ^t When put on Now.	Standing & Running Rigging	"
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. good where tested.				Cont ^d

I am of opinion she is entitled to remain as class'd 9. A. 1.

Samuel Phipps

The Amount of Fee.....£ — : — : } is received by me,

Special..... 2 : 2 : }

Certificate (if required) : 5 : }

Committee's Minute

Character assigned

1st October 1867

Cont^d 9. A. 1.

record G.M.



© 2021

Lloyd's Register Foundation

LON 652-0325

City of Carlisle

REPORT of SURVEY for REPAIRS.

For the year ending 1881

By the Surveyor of the City of Carlisle

Printed by the City of Carlisle

Printed by the City of Carlisle

Printed by the City of Carlisle

Printed by the City of Carlisle



© 2021
Lloyd's Register
Foundation