

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 6 Survey held at London Date 17th Sept 26th 1867
 on the Barque R. F. Turnbull Master J. Cumming
 Tonnage 368 Built at Prince Ed^d Island When built 1864
 By whom built House Owners Gilroy & Br^s
 Port belonging to Dundee Destined Voyage New Zealand
 If Surveyed Afloat or in Dry Dock Fore and Aft dry dock
1/2 time survey

Last Survey, No. 27851 Port London Classed T. A. I.

REPAIRS

Stripped off the whole of the Yellow metal Sheathing drove out some treenails from both sides. also bolts. Lifted the limbers, cut out and open'd air courses, lifted the limbers, lifted the windlass, stripped off linings, the main piece is sound. - renewed all iron bolts found bad or wasted. The treenails driven out for inspection renewed with English Oak. Tanged the chain cables along the deck. they proved sufficient in size and quantity. Caulked from Keel to Gunwale. and resheathed with yellow metal on fell. - Scraped bright in places or where considered necessary.

Present Condition of the

Decks	in good order	Treenails	where seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	"	Masts, Yards, &c. Ex ^d Certified	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from the Deck
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of	3
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	7 1/2 yds	When put on	Standing & Running Rigging	"
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.				
		good where tested				

She has been Survey'd in accordance with the New Rule page 6 Sec² 34. and has been examined inside and outside, and as far as seen, she is sound and in good condition, and the Rules having been fully complied with.

I am of opinion she is entitled to remain

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 :

Certificate (if required) : 5 :

Committee's Minute 8th October 1867

Character assigned 7 A 1

as Class'd T. A. I.
 and to be marked H.T. in the
 Register Samuel Presnors



Lloyd's Register
 Foundation

LON 652-0344

R. J. Linnell

REPORT of SURVEY for REPAIRS.



© 2021

Lloyd's Register
Foundation