

28721

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 117 Survey held at London Date Sept^r 3^d to Oct^r 13th 1864
on the Ship "Matoaka" Master A. Stephens
Tonnage 1323 Built at N Brunswick When built 1853
By whom built Owners Seymour
Port belonging to London Destined Voyage New Zealand
If Surveyed Afloat or in Dry Dock Blackwall dry Dock and East India Dock

Last Survey, No. 26464 Port London Classed A.1. (9.64.)
REPAIRS None done (Rev^d 64.7 yrs)

Sighted bottom Yellow Metal Stripped, Caulked from Keel to middle line of Deck, and bottom resheathed with Yellow Metal on Felt.

Renewed the Main Hatch coamings &c, also Baulking to ditto, with American Oak; unhung the Windlugs and examined Spindle &c; bored and otherwise tested the Keelson near the main hatch (found good) the remainder covered with ballast

Renewed the following spars Viz. Main Yard, the upper Fore-topail yard, and upper mizen-topail yard, with Red-pine; the jib-boom with pitch pine; and mizen mast with yellow pine.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps <u>2</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>5</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>good</u>
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>inspⁿ</u>
Planksheers	Keelsons <u>part seen, bored &c</u>	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 B. 15. 2</u>
Topsides	Ceiling <u>part seen</u>	Cables
Wales	Rudder <u>Had good</u>	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>on</u> When put on <u>now</u>	Standing & Running Rigging <u>pt seen</u>
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>good where tested</u>	

She is now in good and efficient condition, and fit in my opinion to remain Classed. A.1.

Joseph Allen.

The Amount of Fee.....£ — : — : is received by me,
Special.....2.2.0
Certificate (if required) : 5 :

Committee's Minute 29th October 1864

Character assigned Rest 7 1/2 record

