

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 128 Survey held at London Date Aug^r 24th Oct^r 10th 1867
 on the Ship "Harrowby" Master W. Storie
 Tonnage 515 Built at New Brunswick When built 1855
 By whom built _____ Owners Fenwick
 Port belonging to London Destined Voyage Hobart Town
 If Surveyed Afloat or in Dry Dock Union Dry Dock & East India Dock

Last Survey, No. 27034 Port London Classed 7 A. 1. 9. 65
 REPAIRS now done in consequence of Damage - (SS. 65 -)

Renewed on the Starboard side thirteen rough-tree stanchions, seventy-eight feet of main rail, forty-seven feet of plank sheer, and the fore-castle plank sheer, all of Dantzic Red Pine; twenty-one feet of False Keel forward, and the head rails on the Starboard side -

Faulked from Keel to third seam of deck, and the bottom resheathed with Yellow metal upon Felt -

I beg respectfully to call the Committee's attention to their letter of the 29th of August granting the Owner's request to have the Vessel lapse on the Red A at the end of the year -

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways <u>caulked</u> <u>good</u>	Breasthooks and Stenson <u>good</u>	Pumps <u>good</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>three</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings <u>where</u>	Ditto Ditto at other places <u>where</u>	Condition, how ascertained <u>insp^d & inquiry</u>
Plank sheers <u>caulked</u>	Keelsons	Sails <u>where</u>
Sheerstrakes <u>dr</u>	Clamps and Shelves	Anchors No. of <u>3 B 1 S 2 K</u>
Topsides <u>dr</u> <u>seen</u>	Ceiling <u>seen</u>	Cables
Wales <u>dr</u>	Rudder	Hawsers and Warps <u>seen</u>
Plank (Bottom) and Counter <u>caulked</u>	Copper <u>T & Y M</u> When put on <u>now</u>	Standing & Running Rigging

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

She is now in good and efficient condition, fit in my opinion to remain as classed A. 1. to the end of the present year; and as the Rules 2nd Survey Sections 60 & 63 were fully complied with in Sept^r 1865 we beg respectfully to recommend that she be allowed to lapse on the Red A Class for 5 years from that date -

The Amount of Fee.....£ 2: - - is received by me.

Special..... 1: 1: John

Certificate (if required) _____

Committee's Minute 8th November 18 67

Character assigned Cont^d 5 A 1 till 31 December

Then to be A 1 in Red M.A.S. record Y.M. 5.5.45 = 5 years