

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 232 Survey held at London Date 29<sup>th</sup> April to 19<sup>th</sup> May 1866.  
 on the Ship "Asterope" Master A. Stuart  
 Tonnage 601 Built at Aberdeen When built 1859.  
 By whom built A Hall and Co Owners Parker and Co.  
 Port belonging to London Destined Voyage New Zealand  
 If Surveyed Afloat or in Dry Dock Green Up<sup>er</sup> dry Dock and East India St<sup>re</sup>

Last Survey, No. 28237 Port London. Classed B.A.I. (4.6%)  
 REPAIRS Now done. (old rule) H.T. April 1866.

Lighted bottom the Yellow Metal patched, and on account of the entire absence of air courses, recommended that one should be cut in the ceiling, at each end of the hold, on both sides,  $\frac{1}{5}$ <sup>th</sup> the length of the ship, at about the height of the floor heads; which was accordingly done, and found one defective timber on the Starboard side aft, to compensate for which, an iron diagonal strap is added  $6'' \times 1\frac{1}{4}''$  through bolted with Yellow Metal. Timbers lifted nearly all fore and aft, floors and keelson examined. Renewed the Fore Mast with Yellow Pine.

## Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps <u>2</u>
Tomings	Transoms, Pointers, and Crutches	Boats <u>4</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>good</u>
Lower Deck Beams & Fastenings	<u>one defective at aft</u>	Condition, how ascertained <u>inspect and enquiry</u>
Planksheers	Ditto Ditto at other places	Sails
Sheerstrakes	Keelsons	Anchors No. of <u>3 B.W. 2H</u>
Opsides	Clamps and Shelves	Cables
Vales	Ceiling <u>greater pt seen</u>	Hawsers and Warps
Plank (Bottom) and Counter	Rudder <u>Had good</u>	Standing & Running Rigging
General Observations and Opinion,	Copper <u>and Y.M. When put on 1864</u>	
	Caulking of Bottom, Deck, & Waterways.	<u>Good where seen.</u>

She is now in good and efficient condition, and fit in my opinion to remain as Classed Tiz A.I.  
Joseph Keen

The Amount of Fee.....£ — : — : is received by me.

Special.....2-2-0

Certificate (if required) : 5 :

Committee's Minute 26<sup>th</sup> May 18 68

Character assigned 13<sup>th</sup> A 1