

REPORT of SURVEY for REPAIRS.

29269

No. in Reg. Book. **No.** 701 Survey held at London Date May 25th June 1868
 on the Bk "Ensign" Master Duncan
 Tonnage 431 built at Dundee When built 1864
 By whom built _____ Owners Low & Co
 Port belonging to Dundee Destined Voyage Cardiff
 If Surveyed Afloat or in Dry Dock Ratcliff Dry Dock & West India Dock
 Last Survey, No. 27380 Port Lon. Classed 10 A.1.
4.66

REPAIRS now done, The yellow metal sheathing stripped; In anticipation of the Half-time Survey, treenails driven out from various parts of the bottom below the metal line, and the bottom examined, listings cut in the ceiling at the ends for one-fifth her length the hold cleared and a stage made under the hold beams.

The following renewed viz: the Stemson knee with English Oak. four fore hoods of ceiling on the Starboard side and one on the Port side with Dantzic Oak. caulked from the keel to the metal line and the bottom resheathed with yellow metal upon felt. The ends of the vessel salted -

Present Condition of the

Decks	}	good	Treenails	}	good	Windlass and Capstan	}	good
Waterways			Breasthooks and Stemson			Pumps		
Comings	}	firm	Transoms, Pointers, and Crutches	}	where	Boats	}	efficient
Upper Deck Beams & Fastenings			Timbers of the Frame at the openings			Masts, Yards, &c.		
Lower Deck Beams & Fastenings	}	good	Ditto Ditto at other places	}	seen	Sails	}	good
Planksheers			Keelsons			Anchors No. of 3 B 1 S 2 K		
Sheerstrakes	}	where	Clamps and Shelves	}	efficient	Cables	}	efficient
Topsides			Ceiling			Hawsers and Warps		
Wales	}	seen	Rudder	}	efficient	Standing & Running Rigging	}	efficient
Plank (Bottom) and Counter			caulked			Copper T & Y M When put on now		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tested

The Hold and the bottom under the metal sheathing line now examined for Half-time Survey. She is now in good and efficient condition, fit in my opinion to remain as classed 10 A.1.

The Amount of Fee.....£ 1 : — :) is received by me,

Special..... 2 : 2 :)

Certificate (if required) : 5 :)

Committee's Minute 23rd June 18 68

Character assigned 10 A.1

record repair

8/5



© 2019
Lloyd's Register
Foundation
LON 653-0272