

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 357 Survey held at London Date 7th July 14th 1868
 on the Barque Port Royal Master J. Groom
 Tonnage 323 built at Albia When built 1859
 By whom built Adamson Owners C. Dawson
 Port belonging to London Destined Voyage West Indies
 If Surveyed Afloat or in Dry Dock Britannia Dry dock & West India docks.

Last Survey, No. 27084 Port London Classed 10. A. 1.
 66

REPAIRS

Sighted the Yellow metal, and repaired it. Caulked from the Copper line to the Gunwale and round the bulwark Stansions. Fitted new Channels to the masts on the Starb. repaired or made them good on the port side. Introduced an extra beam of Teak on the fore side of Foremast, in the hold. Took off the Hawse boxes. caulked in wake of them, also the seams in wake of Anchor linings. — condemned the fore head of sheer strake on the port side introduced a new one of English Oak. Repaired, and bolted hawse pipes both sides. Bolted, and secured the heel of Whisker boom. or the swivel bolt in connection. Repaired Iron Sillar to Rudder head. —

Shrou'd her in ballast, and with part Cargo on board.

11. 12 Windlass was stripped in Oct^r/68.

Present Condition of the

Decks	good	Treenails	when seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson		"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches		"	Boats	"
Upper Deck Beams & Fastenings	fair	Timbers of the Frame at the openings		"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places		"	Condition, how ascertained	from the deck
Planksheers	"	Keelsons		"	Sails	"
Sheerstrakes	"	Clamps and Shelves		"	Anchors No. of 3	"
Topsides	"	Ceiling		"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	It is good	When put on 1866	Standing & Running Rigging	"

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

This vessel as far as seen appears in good condition. And she is in my opinion entitled to remain as Cleop^a

10. A. 1.

Samuel Presinis

The Amount of Fee.....£ 1 : — : } is received by me.


Special..... 1 : 1 : } *Alf*

Certificate (if required) ————

Committee's Minute 4th August 1868.

Character assigned 10. A. 1.

record repair *WMS*



© 2019

Lloyd's Register
Foundation