

# Composite REPORT of SURVEY for REPAIRS.

29405

No. in Reg. Book. **No.** 668 Survey held at London Date July 1st 18 68  
 on the S. Electra Master J. Howden  
 Tonnage 668 built at Aberdeen When built 1866, 5 mo  
 By whom built Hall Owners Parker & Co  
 Port belonging to London Destined Voyage New Zealand  
 If Surveyed Afloat or in Dry Dock in Green's lower and East India Dock

Last Survey, No. 2289 Port Aberdeen Classed 13 A1  
5.66

## REPAIRS

Stripped Yellow metal sheathing, caulked from keel to metal line and re-sheathed with Yellow metal over felt.  
 Drove out eight bolts on each <sup>between bilges & hold beams</sup> side for survey (these bolts were of galvanized iron and were coated mercurially), four only of these were found to be in any way affected by galvanic action and these only in a slight degree, the remaining twelve being perfect. — Lifted timbers and examined cement, floors, frames &c. all of which were found to be in a satisfactory condition; the ship appears to be very firm, no sign of straining being anywhere apparent.

### Present Condition of the

Decks <u>where seen Good</u>	Greenails <u>Bolts where seen Good</u>	Windlass and Capstan <u>Good</u>
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>from enquiry &amp; as seen from deck</u>
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 B, 1 S, 2 K</u>
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>F.Y.M.</u> When put on <u>1868</u>	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>where tested Good</u>	

Is now in good and efficient condition and in my opinion eligible to remain as classed.

The Amount of Fee.....£ — : — : is received by me,

Special..... 1 : 1 : 0


Certificate (if required) : 5 :

Committee's Minute 28<sup>th</sup> August 18 68

Character assigned 13 A1

*Record of M. 1868*

*John Maxwell*



© 2019

Lloyd's Register Foundation  
 LON653-0373



Electra



© 2019

Lloyd's Register  
Foundation