

Change of Owners & Half time Survey 29466

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 63 Survey held at London Date Aug¹⁶ to Sep¹⁸ 68
 on the Ship "Medway" Master A. M^c Fadzean
 Tonnage 612 built at Scarbro' When built 1845
 By whom built Juddalls Owners Watson Bros
 Port belonging to Glasgow Destined Voyage Bombay
 If Surveyed Afloat or in Dry Dock Ratcliff Dry Dock & East India Dock.

Last Survey, No. 27895 Port London Classed 12A 1
 REPAIRS now done, Rest: 64 - 8 yrs.

The hold cleared, listings cut at each end in the hold for one fifth her length, fillings between truss work removed, stages made, topsides scraped, treenails driven out from various parts, windlass unhung & stripped, chains ranged, and all other requirements of the Half-time Survey Rule. Sec 34 complied with. faulted from keel to gunwale and the bottom resheathed with Yellow Metal upon Felt - Seven shifts of upper deck on the Port side and five on the Starboard side renewed with Dautzic Pine

Present Condition of the		the upper deck caulked, the main		P.T.O.	
Decks	caulked	}	good	Treenails	good those seen
Waterways	caulked			Breasthooks and Stemson	
Comings	caulked			Transoms, Pointers, and Crutches	good
Upper Deck Beams & Fastenings		}	firm	Timbers of the Frame at the openings	
Lower Deck Beams & Fastenings				Ditto Ditto at other places	where
Planksheers	caulked	}	good	Keelsons	
Sheerstrakes	dr			Clamps and Shelves	
Topsides	dr	}	where	Ceiling	
Wales	dr			Rudder	seen
Plank (Bottom) and Counter	caulked			Copper	F & Y M When put on now
				Windlass and Capstan	good
				Pumps	
				Boats	and
				Masts, Yards, &c.	efficient
				Condition, how ascertained	by certificate and inspection from the deck
				Sails	
				Anchors No. of	3 B. 1 S 2 K good
				Cables	and
				Hawsers and Warps	
				Standing & Running Rigging	sufficient

She is now in good and efficient condition, fit in my opinion to remain as classed A.1. and to be marked (HT 1868).

The Amount of Fee.....£ 2 : - : } is received by me, H. Cornish
 Special..... 3 : 3 : }
 Certificate (if required) : 5 : }

Committee's Minute 11th September 18 68
 Character assigned Rest 8 A 1

HT 1868 record

29446 Lon

topmast and jibboom new - one third futtock
renewed with English Oak on the Starboard
Side forward - and two pieces of truss work -

a Third Bower anchor now supplied
and the Testing certificate produced -

	cut	grs	lbs		Tons	cs.
ea Stock	18	3	26			
Stock	3	3	8	tested to	19.19	at Lloyd's Lambuan & A. S. for.
total	22	3	6	No 32 - 16 th	Jan 7.	1866. Signed by Andrew Jack.

W. J. Smith



© 2019

Lloyd's Register
Foundation