

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 326 Survey held at London Date Nov 2nd 18 68
 on the 8 " Ibero " Master Pace
 Tonnage 646 built at Sunderland When built 1855
 By whom built Owners Spence & Co
 Port belonging to London Destined Voyage Bombay
 If Surveyed Afloat or in Dry Dock in Victoria Dock

Last Survey, No. 29420 Port London Classed 10 A1
 cont 65.7 8, 68

REPAIRS in consequence of reported leakage in upper works

Took off a course of Yellow metal sheathing and caulked from thence to waterway seams inclusive; cut away Port cheek and caulked hood ends in way of same; shifted bowsprit shroud plate, the plank to which it was fastened being found split between bolts; a damaged plank in Starboard buttock cut into and a graving piece let in, properly bolted and caulked; re-sheathed upper course where stripped, with Yellow metal; renewed pumps with Redpath's Patent.

Present Condition of the

Decks <u>where seen Good</u>	Treenails <u>where seen Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u> </u>	Breasthooks and Stemson <u>not seen</u>	Pumps <u> </u>
Comings <u> </u>	Transoms, Pointers, and Crutches <u> </u>	Boats <u> </u>
Upper Deck Beams & Fastenings <u>not seen</u>	Timbers of the Frame at the openings <u> </u>	Masts, Yards, &c. <u> </u>
Lower Deck Beams & Fastenings <u> </u>	Ditto Ditto at other places <u> </u>	Condition, how ascertained <u>from enquiry & as seen from decks</u>
Planksheers <u>where seen good</u>	Keelsons <u> </u>	Sails <u> </u>
Sheerstrakes <u> </u>	Clamps and Shelves <u> </u>	Anchors No. of <u>3 B, 1 S, 2 K</u>
Topsides <u> </u>	Ceiling <u> </u>	Cables <u> </u>
Wales <u> </u>	Rudder <u>where seen good</u>	Hawsers and Warps <u> </u>
Plank (Bottom) and Counter <u> </u>	Copper <u>F & M</u> When put on <u>1867</u>	Standing & Running Rigging <u> </u>
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>where tested Good</u>	

Is now in good and efficient condition and in our opinion eligible to remain as classed.

The Amount of Fee.....£ : : is received by me,

Special..... 1 : 1 :

Certificate (if required) : :

Committee's Minute 20th November 1868

Character assigned Cent 7 A 1

John Maxwell
Thos. W. Wain



© 2019

Lloyd's Register
 Foundation
 LON653-0527