

# REPORT of SURVEY for REPAIRS.

and half time survey

No. in Reg. Book. **No.** 727 Survey held at London Date Dec 15<sup>th</sup> 18 68  
 on the S "Star of China" Master Angus  
 Tonnage 794 built at Aberdeen When built 1862  
 By whom built Hall Owners Adamson  
 Port belonging to Aberdeen Destined Voyage Lariff  
 If Surveyed Afloat or in Dry Dock in Ratcliff Cross Dock

Last Survey, No. 28096 Port London Classed 14 A1  
7.68

## REPAIRS

Stripped Yellow metal sheathing; drove out trenails in various parts of ship; scraped bright in parts of topsides; cut out listings at ends of vessel and below clamps in accordance with the rules; timber boards lifted; windlass of iron; chains ranged on deck & found good and sufficient in quantity.

Renewed two bevelling chocks on Starboard side in fore body; seven lengths of ceiling on Starboard & two on Port side of Beak; added a pair of diagonal iron riders extending to upper deck clamps; caulked from Keel to Planksheer & re-sheathed with yellow metal over felt.

### Present Condition of the

Decks <u>when seen Good</u>	Treenails <u>when seen Good</u>	Windlass and Capstan <u>Good</u>
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained <u>from enquiry &amp; as seen from deck</u>
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of <u>3 B.S. 2 K.</u>
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper <u>F.Y.M.</u> When put on <u>1868</u>	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>when tested Good</u>	

Is now in good and efficient condition and in our opinion eligible to remain as classed, and be marked H.T. 68.

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : 28/12/68

Certificate (if required) : :

Committee's Minute 29<sup>th</sup> December 1868

Character assigned 14 A1 11/11/68 recomd W.M. was



© 2019

Lloyd's Register Foundation

LN654-0026



29698 Lon

The timbers of the frame where exposed to view were in good condition

John Maxwell  
Thos. W. Wain

24

I am  
Per  
Am

Ch.

W



© 2019

Lloyd's Register  
Foundation