

Composite Ship REPORT of SURVEY for REPAIRS.

29727

No. in Reg. Book. **No.** 286 Survey held at London Date Nov 30th 1869
 on the ship "Douglas Castle" Master Alex^r M^r Ritchie
 Tonnage 678 built at Glasgow When built 1864
 By whom built _____ Owners James Skinner &
 Port belonging to Glasgow Destined Voyage Hong Kong
 If Surveyed Afloat or in Dry Dock Canal Dry Dock & East India Dock

Last Survey, No. 28231 Port London Classed 1st A. 1.

REPAIRS Now done, the yellow metal sheathing stripped off the bottoms, two yellow metal Nut and Screw Bolts driven out from each side at the bilges, the frames in way of them were quite satisfactory. The Ceiling from bilge to bilge - lifted, the iron work under it scraped, and the bottom thoroughly cemented fore and aft between the frames, leaving a channel at the middle line for the water to reach the pumps; the iron work above the cement painted, and the ceiling replaced. One length of false keel, the Mizzen Mast, and the Mizzen Top mast - renewed. The keel caulked from the keel to the waterways, and her bottom re-sheathed with yellow metal.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Some Bolts - Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>Caulked</u>	Breasthooks and Stemson _____	Pumps _____
Comings <u>Good</u>	Transoms, Pointers, and Crutches _____	Boats <u>Good & sufficient</u>
Upper Deck Beams & Fastenings _____	Timbers of the Frame at the openings _____	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings <u>Good</u>	Ditto Ditto at other places _____	Condition, how ascertained <u>by enquiry and examination from 1864</u>
Planksheers _____	Keelsons <u>Good where seen</u>	Sails _____
Sheerstrakes <u>Caulked</u>	Clamps and Shelves <u>seen</u>	Anchors No. of _____
Topsides _____	Ceiling _____	Cables <u>Good and sufficient</u>
Wales _____	Budder <u>Yellow metal</u>	Hawsers and Warps _____
Plank (Bottom) and Counter <u>Caulked</u>	Copper _____	Standing & Running Rigging _____
	When put on <u>now</u>	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested.

She is now in good and efficient condition, and having examined her 1st Entry Report, and found that her timber material entitle her to the 16th class. I beg respectfully to recommend her class to be raised according to 16th 1. and to have S.S. A. 01. 1869 recorded.

The Amount of Fee.....£ - : - : is received by me,

Special..... 3 : 3 :

Certificate (if required) : : 12/11/69

Committee's Minute 15th January 1869

Character assigned Raise to 16th



© 2019

Lloyd's Register
Foundation

LON654-0044