

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 966 No. 20245 Survey held at London Date 11 February 1869
 on the Ship "Culnaryle" Master A. Morrison
 Tonnage 579 built at Aberdeen When built 1862 - 7 mo
 By whom built Kalb Owners J. Jameson
 Port belonging to Aberdeen Destined Voyage Aberdeen & N. B.
 If Surveyed Afloat or in Dry Dock Kitchie Dry Dock and Afloat

Last Survey, No. 20245 Port London Classed B.A.1

REPAIRS

Hold cleared proper stages made both inside and outside. The timbers and all air courses cleared. outside planking scraped bright in various parts, treenails driven out as per Rule. Windlass of iron, Brown and Warfield's patent, examined and the chain cables ranged on deck for survey.

Stripped Yellow Metal sheathing, added three pairs of diagonal iron straps in the fore cast body and four pairs in the after ditto of $4\frac{1}{2} \times 3\frac{1}{2}$ and extending from the upper deck clamp to floor heads the whole of which are thro' fastened with Yellow Metal bolts. Caulked from keel to gunwale and resheathed bottom with Yellow Metal on belt.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper	Standing & Running Rigging
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	

Ship in good and efficient condition and in my opinion eligible to remain as classed B.A.1 and to be marked H.T.-69.

The Amount of Fee.....£ : : is received by me,

Special.....£ : : Special

Certificate (if required) : : Certificate

Committee's Minute 19th February 1869

Character assigned B.A.1



© 2019

Lloyd's Register Foundation

LON654-0095