

\*29808

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date, first Survey 22<sup>d</sup> March Last Survey April 2<sup>d</sup> 1870  
on the Brig "Aleg" Durnyeat Master Charles Snelling  
Tonnage 199 built at Prince Ed<sup>d</sup> Island When built 1865  
By whom built Longworth Owners Andrews  
Port belonging to London Destined Voyage Perbice  
If Surveyed Afloat or in Dry Dock Duke Shore Dry dock &

Last Survey, No. 29808 Port Lon Classed Y. A. 1. 71.7 in / 69.

## REPAIRS, &c.

chiefly, or partly from damage. by collision.

Renewed ten of the topsimbers on the Port side in midship, height of them from decay. two found split or damaged. - one length of Sheer Strake, one of Covering board or plank sheer, a length of Deck Clamp, six lengths of plank below six of the lodging knees refitted and bolted, and two hanging knees of iron, and one pair of hanging, extra, introduced as compensation. - for a defective timber, which has been pieced or made good as far as practicable. -

Two upper courses of the Yellow Metal sheathing in wake of the damaged timbers all made good and efficient.

New timbers, and new planks, all of Pitchpine.

## Present Condition of the

Decks	good	Treenails	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	from the Deck
ksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of 3 & 4	"
poes	"	Ceiling	"	Cables	"
Wales	"	Rudder <u>good</u>	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper <u>See &amp; ymk</u> When put on <u>1869</u>	"	Standing & Running Rigging	"
Engine Room Skylights	"	Caulking of	good		
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	good		
Scuppers	good			Cargo and Main Hatchways	good
Hatches	good				"

## General Observations and Opinion,

I am of opinion she is entitled to remain as Class'd Y. A. 1.

Samuel Presions

The Amount of Entry Fee.....£ : 10 : is received by me,

Special..... / : /

Certificate (if required) :

Committee's Minute 18

Character assigned



© 2019

Lloyd's Register Foundation

LON654-0102



Allen Burnycall



© 2019

Lloyd's Register  
Foundation