

5th 2619

29578

29935

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 71 Survey held at London Date 5th Jan'y Feby 11th 1869.
 on the Barque Indiana Master G. Cooper
 Tonnage 544 built at Montrose When built 1852
 By whom built — Owners Madams
 Port belonging to London Destined Voyage Singapore
 If Surveyed Afloat or in Dry Dock West India docks.

Last Survey, No. 29578 Port London. Classed Cont^d 1/64. 8. & 1.

REPAIRS

Chiefly from damage. "See Rept of Survey."

Lifted and renewed the whole of the forecastle deck, with 2 1/2 yel^l Pine deals. Introduced several new filling timbers on the Port bow. five new Stansions. New rail. New Covering board. New sheer strake to forecastle. two new fore hoods. and several gore pieces. scarphed one of the Beams. - fitted two new lodging knees. new warping chocks. and leading blocks. new deck hook. bowsprit chock. repaired the head of split stem by fitting and bolting through and through. an iron strap over the damaged part. new topgall's rails to forecastle deck. and new cathead Port side. a quarter and counter timber aft fitted on the Port side, together with two short lengths of covering board. - and some new quick work stuff. fore^d and aft. caulked the forecastle deck. and the bows.

A new Bowsprit with fibbrom flying fibbrom. New Foremast. New main mast. Topmast topgall's mast. Royal Mast. Fore yard. Topgall's yard. martingale. Head pump. Head stays. back stays. and most of the rigging to Fore mast. & Bowsprit in connection. New long boat. New Quarter boat. -

Present Condition of the

Decks	good	Treenails	Where seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	two new.
Upper Deck Beams & Fastenings	firm	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	part new
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	from the Deck
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors	No. of 3 & 4
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	Feb 4 yml	When put on 1867	Standing & Running Rigging	"

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

I am of opinion she is entitled to remain as class'd

8. A. 1 in 64.

Samuel P. Brown

The Amount of Fee.....£ 2:--: is received by me,

Special.....: :
 Certificate (if required) : 5: }

Committee's Minute 26th February 18 69

Character assigned Cont^d 8 A

second damage repairs



Lloyd's Register Foundation

LONG54-0128

Indiana

This vessel altho' she had been recently dock'd and fixed
out. and wind bound, from the ~~Storm~~ and collision, put back,
with passengers, to make good the repairs. so that under the circumstances
I had no opportunity of surveying her, in reference to the "half-time
Survey." -

Samuel Mervin

Feb'y 25th 1869



© 2019

Lloyd's Register
Foundation