

REPORT of SURVEY for REPAIRS.

30016

No. in Reg. Book. **No.** 703 Survey held at London Date 17th March 31st 1869
 on the Barque Ensign Master J. Duncan
 Tonnage 431 built at Dundee When built 1864
 By whom built Jay & Co. Owners Andrew Low & Co. See Note annexed
 Port belonging to Dundee Destined Voyage Cardiff
 If Surveyed Afloat or in Dry Dock West India Docks and Blackwall Basin

Last Survey, No. 29269 Port London Classed 10. A. 1.
6.68

REPAIRS

Unhung and stripped the Windluffs. the main piece proved sound. Scraped the outside planks bright where necessary, in sections tw'n the copper line and Gunwale. opened the air courses tw'n decks and drifted out treenails from various places. Cut out some slight defects from the teak planks on the port side in the Wale. and received between three and four hundred treenails tw'n or from the fore part of fore rigging to the after part of the main rigging. and the same number on the Starb^d side, which were found slack.

Lifted the chain cables from the lockers. Ranged them along the deck and found them sufficient in size, and in quantity also.

Present Condition of the

Decks	<u>good</u>	Treenails	<u>part new</u>	<u>good</u>	Windlass and Capstan	<u>in good order</u>
Waterways	<u>"</u>	Breasthooks and Stemson	<u>"</u>	<u>"</u>	Pumps	<u>"</u>
Comings	<u>"</u>	Transoms, Pointers, and Crutches	<u>"</u>	<u>"</u>	Boats	<u>"</u>
Upper Deck Beams & Fastenings	<u>"</u>	Timbers of the Frame at the openings	<u>"</u>	<u>"</u>	Masts, Yards, &c.	<u>"</u>
Lower Deck Beams & Fastenings	<u>"</u>	Ditto Ditto at other places	<u>"</u>	<u>"</u>	Condition, how ascertained	<u>from the Deck</u>
Planksheers	<u>"</u>	Keelsons	<u>"</u>	<u>"</u>	Sails	<u>"</u>
Sheerstrakes	<u>"</u>	Clamps and Shelves	<u>"</u>	<u>"</u>	Anchors No. of <u>3</u>	<u>"</u>
Topsides	<u>"</u>	Ceiling	<u>"</u>	<u>"</u>	Cables	<u>"</u>
Wales	<u>"</u>	Rudder	<u>efficient</u>	<u>"</u>	Hawsers and Warps	<u>"</u>
Plank (Bottom) and Counter	<u>"</u>	Copper	<u>3/4" Gynk</u>	<u>When put on 1869</u>	Standing & Running Rigging	<u>"</u>

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

She has been surveyed now partly in ballast, or as far as practicable, inside and outside, and the half time Survey Rule "Sec^d 34" having been now completed. (See Report No^o 29269, I am of opinion she is entitled to remain as classed 10. A. 1. and to be marked H.T. in the Reg^r. Samuel Presons

The Amount of Fee.....£ : : } is received by me,
 Special..... / : / : }
 Certificate (if required) : 5 : }

Committee's Minute 9th April 1869

Character assigned 10A 1 11.11.69 record

Ensign

REPORT OF THE COMMITTEE ON THE PROGRESS OF THE WORK OF THE LLOYD'S REGISTER

REPAIRS



© 2019

Lloyd's Register Foundation