

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 115 Survey held at London Date 12th April 1869
on the bark "Samuel" Master R. Higzell
Tonnage 426 built at Sunderland When built 1861 - 8 mo
By whom built Higgle & Co. Owners Sir J. Pegg
Port belonging to London Destined Voyage Aden
If Surveyed Afloat or in Dry Dock Limeskin dry dock and afloat

Last Survey, No. 28241 Port London Classed B A 1

REPAIRS Hold cleared proper stages made both inside and outside the timbers and all air courses cleared. Scraped bright from metal line of gunwale all fore and aft on each side. Reenails driven out as per Rule. Windlass unhung with linings stripped and chain cables ranged on deck for examination.
For Damage. Stripped Yellow Metal Sheathing. Sides re-sheathed all fore and aft on each side with Australian hard wood and locust. hung in shores caulked from keel to gunwale and resheathed bottom with Yellow Metal on felt.
For Damage. Strake of deck next waterway on each side extending from Post of Newcastle to end of deck. 3 1/2 in thick and fastened with galvanized iron clamps. Caulked waterway seams and two beams of deck next them.

Present Condition of the
Decks Good Treenails Good Windlass and Capstan Good
Waterways Good Breasthooks and Stems Good Pumps Good
Comings Good Transoms, Pointers, and Crutches Good Boats Good
Upper Deck Beams & Fastenings Good Timbers of the Frame at the openings Good Masts, Yards, &c. Good
Lower Deck Beams & Fastenings Good Ditto Ditto at other places Good Condition, how ascertained Seen from the deck
Planksheers Good Keelsons Good Sails Good
Sheerstrakes Good Clamps and Shelves Good Anchors No. of 2 Good
Topsides Good Ceiling Good Cables Good
Wales Good Rudder Good Hawseers and Warps Good
Plank (Bottom) and Counter Good Copper Good When put on Now Standing & Running Rigging Good
General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested.

Is now in good and efficient condition and in my opinion eligible to remain as classed and she marked
 H.T. 69.

The Amount of Fee.....£ / : : is received by me,
Special.....£ : :
Certificate (if required) : :
Damage : :
WMC 14/4/69

Committee's Minute 16th April 18 69

Character assigned B A 1 H.T. 69
 record damaged repair