

30042

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 19 Survey held at London Date 17th April 1869  
on the  bark "Ballarat"  Master Joseph Allan  
Tonnage 685 built at Aberdeen When built 1852  
By whom built Dothief Owners Tayne & Co  
Port belonging to London Destined Voyage New Zealand  
If Surveyed Afloat or in Dry Dock Bull Head dry dock and Afloat.

Last Survey, No. \_\_\_\_\_ Port \_\_\_\_\_ Classed MAI.

**REPAIRS** Hold cleaned proper shapes made both inside and outside; the timbers and all air courses cleared, outside planking scraped bright from metal line to gunwale all fore and aft on each side. Treennails driven out as per Rule, Windlass unhung, iron linings stripped and chain cables ranged on deck for examination. Stripped Yellow Metal sheathing, one upper deck beam scarphed of English Oak. one pair of iron hanging knees to Hold-beam thro'fastened with Yellow Metal bolts. three planks of upper deck renewed of Yellow Pine. Caulked from keel to third beam within the waterway. beam and resheathed bottom with Yellow Metal on felt.

|                                   |  |  |
|-----------------------------------|--|--|
| Present Condition of the          |  |  |
| Decks                             | Treenails  | Windlass and Capstan <u>Good</u>                     |
| Waterways                         | Breasthooks and Stenson  | Pumps  |
| Comings                           | Transoms, Pointers, and Crutches                                 | Boats  |
| Upper Deck Beams & Fastenings     | Timbers of the Frame at the openings                             | Masts, Yards, &c.                                    |
| Lower Deck Beams & Fastenings     | Ditto Ditto at other places                                      | Condition, how ascertained <u>seen from the deck</u> |
| Planksheers                       | Keelsons   | Sails  |
| Sheerstrakes                      | Clamps and Shelves   | Anchors No. of <u>3</u> <u>Good</u>                  |
| Topsides                          | Ceiling  | Cables <u>and</u>                                    |
| Wales                             | Rudder   | Hawsers and Warps <u>sufficient</u>                  |
| Plank (Bottom) and Counter        | Copper <u>At Ym</u> When put on <u>now</u>                       | Standing & Running Rigging                           |
| General Observations and Opinion, | Caulking of Bottom, Deck, & Waterways. <u>Good where tested.</u> |  |

Is now in good and efficient condition and in my opinion eligible to remain as classed and be marked H.I. 69.

The Amount of Fee.....£ 2 : - : is received by me,  
Special.....£ 2 : 2 :  
Certificate (if required) : 5 :

Committee's Minute 20th April 18 69  
Character assigned Good & Fair

H. H. Turner.

HT 69  
recd G. M. W. S.