

REPORT of SURVEY for REPAIRS.

30198

No. in Reg. Book. **No.** 109 Survey held at London Date 11th June 23rd 1869
 on the Ship Geologist. Master Michael Clarke
 Tonnage 854 built at Liverpool When built 1859
 By whom built Chaloner Owners Harrisons
 Port belonging to Liverpool Destined Voyage Hong Kong.
 If Surveyed Afloat or in Dry Dock Limekiln Dry dock and East India Docks

Last Survey, No. 20953 Port Liv. Classed 13.A.1. H. Tin/67.

REPAIRS

Chiefly from damage. See Report.

Stripped off the whole of the Yellow metal sheathing. Hung her in shores. Renewed the foremast length of Main Keel, also the false keel, and a short length of false keel at the after end. - Renewed the Gripe piece, two lengths of Plank next the keel, dropped off the bruised stem and put all in order as before. Caulked from keel to keel or over all, and sheathed with Yellow metal on felt. -

Supplied her with a Kedge Anchor of 5 cwt. in lieu of one lost, and a 5ms rope. -

Present Condition of the

Decks	good	Treenails	as far as seen	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stenson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained	"
Planksheers	"	Keelsons	"	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of <u>2</u>	"
Topsides	"	Ceiling	"	"	Cables	"
Wales	"	Rudder	efficient	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	felt & gmk When put on	now.	Standing & Running Rigging	"
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>good.</u>					

I am of opinion she is entitled to remain as Class'd

13.A.1.
Samuel Presons


The Amount of Fee.....£ 2 : - : is received by me,
£6.6 the damage
 Special..... 2 : 2 : 20/

Certificate (if required) : :

Committee's Minute 25th June 18 69

Character assigned 13.A.1

record damage repair



© 2019

Lloyd's Register
 Foundation

LON654-0344

Geology

REPORT OF THE COMMITTEE ON THE GEOLOGY OF THE STATE OF NEW YORK

Presented to the Legislature at the Session of 1881-82
By the Committee on the Geology of the State of New York
Albany, N. Y.: J. B. Nichols, Printer, 1882.

ALBANY, N. Y.: J. B. NICHOLS, PRINTER, 1882.

ALBANY, N. Y.: J. B. NICHOLS, PRINTER, 1882.

ALBANY, N. Y.: J. B. NICHOLS, PRINTER, 1882.



© 2019

Lloyd's Register Foundation